

EATON COUNTY REMONUMENTATION

FILED

DEC 1 2 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 14 PM 12:46

Form with fields: For Corners in EATON (county), Located In, Corner Code #, 1. Public Land Survey WEST 1/4 CORNER SECTION 18 BELLEVUE TOWNSHIP ON RANGE LINE, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No, Recorded Plat, 5. Private Claims

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Liber 3 pg 818

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 8 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Table with 13 rows and 12 columns (A-L) containing numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOTE: CLOSING 1/4 CORNER WAS NOT SET BY GENERAL LAND OFFICE SURVEY. ITEMS 1 AND 2 BELOW REFER TO M-6 T1N R7W, THE CORRESPONDING 1/4 CORNER.

- 1. GENERAL LAND OFFICE: JOHN MULLETT, D.S., (NO MONTH) 1825 (T1N, R6W, P. 494), "40.00 SET 1/4 SEC POST" IRONWOOD 7 S4 1/2W 27 W. OAK 12
2. GENERAL LAND OFFICE SURVEY: JOHN MULLETT, D.S., DEC. 1825 (T1N, R7W, P. 5) "40.00 SET POST 1/4 SECTION CORNER" BEECH 6 N40W 06 Do. 6 S37 1/2W 22

*** NOTE: RANGE LINE BETWEEN T 1 N, R6 & 7W WAS APPARENTLY RUN ON TWO SEPARATE OCCASIONS ***
3. NO MENTION OF THIS CORNER COULD BE FOUND IN THE RECORDS OF THE COUNTY SURVEYOR OF BARRY OR EATON COUNTIES.

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION AT EITHER STANDARD CORNER OR CLOSING CORNER. TRAVERSED ALL OF SECTION 18, INCLUDING STANDARD CORNERS. EXCAVATION AT APPARENT STANDARD CORNER POSITION REVEALED TRACES OF OLD MONUMENTATION IN THE FORM OF A SCATTERING OF COAL BETWEEN THE CLAY GRADE AND THE GRAVEL. EXCAVATION AT CLOSING CORNER REVEALED NO EVIDENCE OF PREVIOUS MONUMENTATION. ACCEPTED FOUND COAL AS BEST AVAILABLE EVIDENCE OF STANDARD CORNER POSITION. ACCEPTED MID-POINT BETWEEN A-5 AND A-7 ON RANGE LINE AS PROPER POSITION OF CLOSING CORNER. SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT AT MID POINT (A-5 TO A-7) ON RANGE LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH PLASTIC CAP.
SET 20d NAIL W/REMON TAG IN THE TOP CENTER OF A WOOD FENCE POST S20°W 88.73'
SET 20d NAIL W/REMON TAG IN THE TOP CENTER OF A WOOD CORNER POST S35°W 51.96'
SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A 26" OAK S08°E 188.34'
SET 1/2" x 18" IRON W/TRaverse POINT CAP N54°E 43.21'
SET 1/2" x 18" IRON W/TRaverse POINT CAP S43°E 60.02'
M-6, T1N, R7W, ASSYRIA TOWNSHIP, LIES SOUTH 42.40'
1/2" IRON W/TRaverse POINT CAP (BL1-52-149-TP) LIES S32°W 21.23'
2'+/- WEST OF NORTH-SOUTH GRAVEL CENTERLINE (CURTIS ROAD)
12'+/- NORTH OF GRAVEL CENTERLINE EAST (LINK HIGHWAY)
42'+/- NORTH OF FENCE LINE WEST



P.A. 345 EATON COUNTY.
PEER APPROVED 7/22/97 M

Signed by [Signature]
Surveyor's Michigan License No 31602

Date 8-15-97