

REMONUMENTATION

EATON COUNTY REMONUMENTATION

FILED

DEC 18 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

copy
97 DEC -2 AM 10:30

For Corners in EATON Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 1N R 6W _____ B-1
NORTH 1/4 CORNER T _____ R _____ _____
SECTION 6 T _____ R _____ _____
BELLEVUE TOWNSHIP T _____ R _____ _____
ON TOWNSHIP LINE

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 868

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Brian Reynolds, in a field survey on 31 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1825 (T1N, R6W, P.492) "40.00 SET 1/4 SEC POST" W. OAK 9 N52E 19 BEECH 6 N32W 24
- 2. COUNTY SURVEYOR RECORDS: OSCAR CHURCH, 8 JUNE, 1878 (V. 1, P.231), "ESTABLISHED 1/4 ACCORDING TO LAW, SET STAKE" NO WITNESSES

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. CORNER LIES IN A SLIGHT CUT AREA, 1'-2'+/-, TRAVERSED ALL OF SECTION 6, TYING IN OCCUPATION THROUGHOUT AND A-13 & B-13 KALAMO TOWNSHIP STANDARD CORNERS). INTERSECTED 1/4 LINE OCCUPATION FROM SOUTH WITH TOWNSHIP LINE (A-13 TO B-13).

ACCEPTED THIS AS BEST METHOD OF CORNER RESTORATION.

SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 24" IRON WITH PLASTIC CAP) AND INSTALLED MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 24" IRON) WITH PLASTIC CAP.
- SET "PK" NAIL WITH PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S5°W 55.85'
- SET 1/2" X 18" IRON WITH "TRAVERSE POINT" CAP S32°W 27.46'
- SET 1/2" X 18" IRON WITH "TRAVERSE POINT" CAP S41°E 31.58'
- SET 1/2" X 18" IRON WITH "TRAVERSE POINT" CAP N57°E 15.70'
- SET 1/2" X 18" IRON WITH "TRAVERSE POINT" CAP N56°W 14.97'
- 5'+/- NORTH OF EAST-WEST PAINTED CENTERLINE
- N LINE WITH OCCUPATION LINE SOUTH
- 3-13, T2N, R6W, LIES S89°14'07"E 83.13'
- 4-1, T1N, R6W (TOWNSHIP CORNER) LIES N89°14'06"W 2881.45'
- 3-2, T1N, R6W LIES S00°35'13"W 2764.65'
- 2-1, T1N, R6W LIES S89°14'05"E 2648.80'

P.A. 345 EATON COUNTY,
PEER APPROVED 9/18/97 M



Signed by Brian Reynolds
Surveyor's Michigan License No 31602

Date DEC 15, 1997