

EATON COUNTY REMONUMENTATION

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 14 PM 12:46

For Corners in <u>EATON</u> (county)	Located In:	Corner Code #
1. Public Land Survey CENTER 1/4 CORNER OF SECTION 18 BELLEVUE TOWNSHIP	T <u>1N</u> R <u>6W</u>	<u>B-6</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No _____, Recorded Plat _____		
5. Private Claims _____		

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Liber 3 pg 819

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 10 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6		17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
2. NO RECORD OF THIS CORNER COULD BE FOUND IN THE COUNTY SURVEYOR'S RECORDS.

*** NO HISTORICAL INFORMATION; PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. TRAVERSED OF ALL OF SECTION 18, TYING IN OCCUPATION THROUGHOUT SECTION. COMPUTED POSITION AT INTERSECTION OF 1/4 LINES. EXCAVATION AT INTERSECTION OF 1/4 LINES REVEALED NO EVIDENCE.
SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH PLASTIC CAP.

- SET 20d NAIL W/PLASTIC TAG IN THE TOP CENTER OF A WOOD FENCE POST N25°W 26.42'
- SET 20d NAIL W/PLASTIC TAG IN THE TOP CENTER OF A WOOD FENCE POST N51°W 38.30'
- SET 20d NAIL W/PLASTIC TAG IN THE TOP CENTER OF A WOOD FENCE POST N71°W 72.62'
- 1/2" x 18" IRON W/TRVERSE POINT CAP (BL1-53-151-TP) N88°55'06"W 382.54'
- SET 1/2" x 18" IRON WITH CAP (INSCRIBED "REYNOLDS 31602") S00°41'41"W 33.00'
- SET 1/2" x 18" IRON WITH CAP (INSCRIBED "REYNOLDS 31602") N00°41'41"E 33.00'
- CORNER LIES 4'+/- NORTH OF EAST-WEST GRAVEL CENTERLINE (LINK HIGHWAY)
- 1'+/- EAST OF NORTH-SOUTH FENCE LINE
- A-6 LIES N89°58'34"W 2746.78'
- B-5 LIES N00°41'41"E 2661.12'
- C-6 LIES S89°58'34"E 2657.04'
- B-7 LIES S00°41'41"W 2635.11'

P.A. 345 EATON COUNTY
PEER APPROVED 7/22/97 M



Signed by [Signature]
Surveyor's Michigan License No 31602

Date 8-15-97