



PART "A" CONTINUED

2. Corner identified on May 9, 1861 as a "Stake and iron for cor. Old ? taken from the fire place of the old man Linsley, the head to the West feet to the East" with no witnesses given, in a marginal note in the Eaton County Road Commissions copy of the Original Government Survey notes.
3. Corner identified in 1917 by H.A. Williams as a "stone for Cor. T2 & 3N, R3 & 4W". Witnessed by: Anc. Post N48 1/2°E 33 1/2', Anc. Post S52 1/2°W 28', Anc. Post S35 1/2°E 43.4'.
4. Corner referred to in a survey by O.G. Church, County Surveyor, on February 8, 1876 (vol. 2, page 2 and 3 County Surveyor Records) as "Corner lost, established cor.", with no monument or witnesses given.
5. Corner identified in a survey by O.G. Church, County Surveyor, in 1876 (vol. 2, page 24 and 25 County Surveyor Records) and identified as a stake with no witnesses given.
6. Corner identified in a survey by Morell E. Newcomb, County Surveyor, in January, 1909 (vol. 4, page 36 and 37, vol. 5, page 36 and 37 County Surveyor Records) and identified as a "stone with wire around it". Witnessed by; fence post NE'ly 33.20 feet, fence post SE'ly 43.20 feet.
7. Marvin F. Fouty, P.S. #18989, recorded corner on 02/10/74 in Liber 2 of Corners, Page 99, as "found angle iron buried 2" in gravel at intersection of Kinsel Hwy. and Royston Rds., from witnesses by Surveyor K.D. Fluke. Witnessed by: Found P.K. nail East side P.P. SSE 57.67', Found P.K. nail West side P.P. SW 45.64', Found P.K. nail East side 14" Maple, NE 37.25'.
8. Maurice H. Mahieu, P.S. #28414, recorded corner on 03/5/85 in Liber 2 of Corners, Page 948, as "found angle iron at intersection of Kinsel Hwy. and Royston Rds". Witnessed by: Larry Bryan Tag in 36" Maple tree ENE 84.63 feet, Larry Bryan Tag in power pole SW 63.51 feet, Larry Bryan Tag in 14" Maple tree NE 37.25 feet.
9. Austin C. Williams, P.S. #21275, recorded corner on 06/26/85 in Liber 2 of Corners, Page 967, as a 3/4" pipe at intersection of centerlines of Royston Road and Kinsel Hwy. Witnessed by: Bryan Survey Tag SE/S 15" Maple N40°E 37.22', Bryan Survey Tag S/S 60" Oak N80°E 84.60', Nail and tag NW/S power pole S35°W 63.22'.
10. Corner shown on a survey by Marvin F. Fouty P.S. #18989, dated October 8, 1973, and recorded in Liber 1 of Surveys, Page 620 and 621 Eaton County Records, with the same monument and witnesses listed in item #7.
11. Corner shown on a survey by Larry A. Bryan P.S. #25832, dated September 14, 1983, and recorded in Liber 5 of Surveys, Page 181 and 182 Eaton County Records, referencing item #8.
12. Corner shown on an unrecorded survey by Kay D. Fluke P.S. #18988, dated September 10, 1992, with the same monument and witnesses listed in item #8.

PART "B" CONTINUED

(Recorded 2715.90 feet County Surveyor Records), East 2457.40 feet to B-13 Windsor Township (Recorded 2454.21 feet County Surveyor Records), North 2628.92 feet to A-12 Windsor Township (Recorded 2629.44 feet County Surveyor Records). Accepted position of 2" angle iron as the perpetuated location of M-13 and set 3/4" bar and cap stamped P.A. 345 #25832 0.5' below gravel surface.