

DEC 12 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in Eaton Rapids Township

Table with columns: EATON COUNTY, Located In: (T 2N R 3W), Corner Code # (L-7). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

97 DEC -2 AM 10:06

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 854
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Maurice H. Mahieu, in a field survey on Sept. 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-12. Contains numerical data for survey points.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original corner was set by Hervey Parke D.S. "Set 1/4 Sec. Post at a (39.98 1/2) distance on True line. Beech 10" S 64° W 22; Beech 6" N 46° E 16.
2. Marginal note in GLO notes "Stone".
3. LCRC by Ronnie Lester #18998 in Liber 1, Page 191, Recorded November 27, 1972. "Found 3/4" pipe centerline Bunker Road on old fence line South measurement East and West in close accord with original government measurement. Nail West side fence post South 21.40 feet; Nail South side 12" Walnut WNW 84.70 feet; Nail in North side 20" Walnut WSW 88.95 feet.
4. An Act 132 survey recorded in Liber 1, Page 215 on Oct. 13, 1972 by Ronnie M. Lester, P.S. #18998. Monument and witnesses same as A-3. Measured 2634.47 to K-7.
5. An Act 132 survey recorded in Liber 2, Page 431 on Sept. 21, 1977 and Liber 2, Page 432 by Laverne J. Hendryx calls for corner but did not give monument or witnesses.
6. An Act 132 survey recorded in Liber 2, Page 599 on Aug. 4, 1978 by Ronnie M. Lester P.S. 18998 calls for same monument and witness as A-3. Measured 2633.87 to K-7.
7. An Act 132 survey recorded in Liber 2, Page 643 on Aug. 26, 1978 by Richard W. Steadman, P.S. 11370 calls for same monument and witness as A-3.
8. An Act 132 survey recorded in Liber 2, Page 923 on April. 27, 1979 by Ronnie M. Lester P.S. 18998 calls for same monument and witness as A-3. Measured 2633.87 to K-7.

(Continued on Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 20" iron pipe in Bunker Highway, mature North-South treeline to the South. Found the following witness: Nail and tag #18998 North side 36" Walnut S 74° W 88.64 feet; Nail and tag #18998 East side 12" Hickory 32° W 24.15 feet; Nail and tag #18998, East side 12" Hickory S 02° W 24.18 feet; Nail and tag #30090 (Dave Lohr) Northwest side Power Pole N 65° E 57.90 feet; Nail and tag #18998 South side 24" Walnut N 73° W 84.46 feet. Excavated 30" diameter Hole to a depth of 36 inches. Found no other evidence. Replace 3/4" pipe with 3/4" x 24" iron pin with cap stamped "PA 345 PS 28414". This surveyor believes that the 3/4" pipe is the perpetuated location of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" x 24" iron pin with cap stamped "PA 345 PS 28414"; witnessed by: Found Nail and Tag #18998 East side 12" Hickory S 02° W 24.18 feet Found Nail and Tag #18998 North side 36" Walnut S 74° W 88.64 feet Found Nail and Tag #18998 South side 24" Walnut N 74° W 84.46 feet Found Nail and Tag #30090 Northwest side Utility Pole N 65° E 57.90 feet.

Signed by [Signature] Date 11-25-97
Surveyor's Michigan License No. 28414



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 1971
REVISED MAY 14, 1981

P.A. 345 EATON COUNTY
PEER APPROVED 10/14/97 m

REVISED JAN.
REVISED OCT.

L-7 Continued

9. An Act 132 survey recorded in Liber 2, Page 922, re-recorded in Liber 2, Page 925 on May 11 and 24, 1979 by George M. Young, P.S. #17640 calls for same monument and witness as A-3. Measured 2633.87 to K-7.
10. An Act 132 survey recorded in Liber 2, Page 995 on July 7, 1979 by A. Williams, P.S. 21275 calls for same monument and witness as A-3. Measured 2633.87 to K-7.
11. An Act 132 survey recorded in Liber 3, Page 502 on March 16, 1983 by George Young, P.S. #17640 calls for same monument and witness as A-3.
12. An Act 132 survey recorded in Liber 3, Page 866 on Aug. 13, 1985 by Peter Beaver, P.S. 25828 calls for same monument and witness as A-3. Measured 2633.87 to K-7.
13. An Act 132 survey recorded in Liber 4, Page 891 on March 27, 1990 by Larry Bryan, P.S. 25832 "Found 3/4" pipe 3' ± South centerline Bunker Highway on fence line South; Witnessed by: Found Nail and tag #18998 South side 12" Walnut N 70° W 85.00 feet; Found Nail and tag #18998 North side 24" Walnut S 70° W 88.85 feet; Found Nail and tag #30090 Northwest side Utility Pole, N 70° E 57.94 feet.
14. An Act 132 survey recorded in Liber 5, Page 325 on May 3, 1991 by Ronnie M. Lester #18998 "3/4" pipe witnessed by: Set Nail and tag in South side 18" Walnut 292° Az 84.5'; Set Nail and tag in North side 30" Walnut 258° Az 88.8'; Set Nail and tag in East side 10" Pignut 185° Az 24.2'; Found Nail and tag #30090 in Northwest side Utility Pole 70° Az 57.9'; Northeast corner frame house #11520 199° Az 134.0'. Measured 2633.87 to K-7.
15. An Act 132 survey recorded in Liber 6, Page 40 on July 17, 1995 by Ronnie M. Lester, P.S. 18998 monument and witness same as A-14. Measured 2633.87 to K-7.
16. An Act 132 survey recorded in Liber 6, Page 373 on August 30, 1996 by Larry Bryan, P.S. #25832 "Found 3/4" pipe centerline of Bunker Highway on treeline South. Found Nail and flagging South side 12" Walnut N 70° W 84.75 feet; Found Nail and flagging North side 20" Walnut S 70° W 88.94 feet; Set P.K. Nail East side Power Pole S 05° W 46.82 feet.
17. An Act 132 survey recorded in Liber 6, Page 44 on July 17, 1995 by Ronnie M. Lester, P.S. 18998. Monument and witness same as A-14. Measured 2633.87 to K-7.
18. An Act 132 survey recorded in Liber 6, Page 706 on Jan. 31, 1997 by Marvin Fouty, P.S. 18989. No monument or witness given. Measured 2633.87 to K-7.