

DEC 1 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Eaton Rapids Township

| EATON COUNTY | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>2N</u> R <u>3W</u> | <u>L-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
copy LIBER 3 PAGE 85
 97 DEC -2 AM 10: 06

LINDA M. TWITCHELL
 REGISTER OF DEEDS
 EATON COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on Oct. 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 1 | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. Corner was not set as a part of the original government survey.
 2. County Surveyor J. H. Gibbons in Vol. 1, Page 57 in June 1869 calls for stone.
 3. LCRC recorded in Liber 2, Page 263 on July 25, 1975 by Ronnie M. Lester, P.S. #18998 "Found old fence intersection and accepted as corner set above measured 40.06 chains East to East 1/4 Corner as called for in survey above. (Refers to Gibbons Survey measured South also in close accord. Set 1/2" bar & cap at base of anchor post at fence intersection; Nail and Tag in Northwest side 8" Cottonwood SE 9.68 feet; Nail and Tag in West side 12" Cottonwood South 16.95 feet; Nail and Tag in Northeast side 12" Cottonwood WNW 5.70 feet.
 4. LCRC recorded in Liber 2, Page 277 on August 27, 1975 by Ronnie M. Lester, P.S. 18998 is same as A-3.
 5. Eaton County Road Commission grid map calls for witness of 7" Beech NW 14 lks and 7' Beech SWW 4 lks.
 6. An Act 132 survey recorded in Liber 1, Page 924 on August 26, 1975 by Ronnie M. Lester, P.S. 18998. Monumentation and witness same as A-3. Measured 2660.23 to L-9.
 7. An Act 132 survey recorded in Liber 3, Page 379 on October 15, 1981 by Richard W. Steadman, P.S. 11370. Monumentation and witness same as A-3. Measured 2625.00 to K-8, 2660.51 to L-9.
 8. An Act 132 survey recorded in Liber 2, Page 748 on October 25, 1978 by Richard W. Steadman, P.S. 11370. Monumentation and witness same as A-3.
 9. An Act 132 survey recorded in Liber 2, Page 922 and re-recorded in Liber 2, Page 925 on May 11 and 24, 1979 by George M. Young, P.S. 17640. Monumentation and witness same as A-3. Measured 2624.84 to K-8, 2634.75 to L-7.

(Continued On Back)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 1/2" iron rod with cap #18998 at intersection of downed North, South, East and West fence lines. Corner falls in location of old fence post. Found Nail and tag #18998 Northeast side 15" Sassafras (Lester calls out as Cottonwood) N 80° W 5.70 feet; Centerline 18" Sassafras (Lester's Cottonwood) South 16.9 feet; Centerline Twin 15" Sassafras (Lester's Cottonwood) S 50° E 9.70 feet; Replaced 1/2" iron rod with 3/4" iron pin with cap stamped "PA 345, PS 28414". The found 1/2" iron rod and the set 3/4" iron pin area believed to be the position of Gibbons corner and is the best perpetuated location.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 3/4" iron pin with cap stamped "PA 345 PA 28414" in place of Found 1/2" iron rod, witnessed by:
 Set Nail and Tag #28414 Northeast side 15" Sassafras N 80° W 5.70 feet
 Set Nail and Tag #28414 West side 18" Sassafras South 16.92 feet
 Set Nail and Tag #28414 North side Twin 15" Sassafras S 50° E 9.72 feet
 Set Nail and Tag #28414 North side 21" Hickory East 29.47 feet

Signed by Maurice H. Mahieu
 Surveyor's Michigan License No. 28414

Date 11-25-97



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
 REVISED MAY 14, 1975
 REVISED JAN. 1975
 REVISED OCT.

P.A. 345 EATON COUNTY
 PEER APPROVED 10/14/97 M

L-8 Continued

10. An Act 132 survey recorded in Liber 3, Page 502 on May 16, 1983 by George M. Young, P.S. 17640 . Monumentation and witness same as A-3. Measured 2634.75 to L-7.
11. An Act 132 survey recorded in Liber 5, Page 286 (date of recording illegible) by Richard W. Steadman, P.S. 11370. Monumentation and witness same as A-3.
12. An Act 132 survey recorded in Liber 5, Page 536 on July 1994 by Pete Beaver, P.S. 25828 calls for corner but no monumentation or witnesses shown. Measured 2660.25 to L-9.
13. An Act 132 survey recorded in Liber 6, Page 373 on August 3, 1996 by Larry Bryan, P.S. 25832. Monumentation and witness same as A-3. Measured 2634.87 to L-7.
14. An Act 132 survey recorded in Liber 6, Page 535 on November 25, 1996 by Pete Beaver, P.S. 25828. No monumentation or witnesses shown. Measured 2660.25 to L-9.