

DEC 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Eaton Rapids Township

| EATON COUNTY | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>2N</u> R <u>3W</u> | <u>M-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED

Copy

97 DEC -2 AM 10:07

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 866
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on Sept. 26, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|---|----|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | | 36 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- Original GLO corner was set by Hervey Parke, D.S. in 1826; Bearing Trees 7" Beech N 17° W 16 lks; 5" Ironwood S 33 1/2° W 32 lks.
- LCRC in Liber 1, Page 383 recorded on Feb. 5, 1974 by Richard W. Steadman, P.S. 11370 Dug large hole but found nothing. Corner may have been destroyed by road construction. Re-established corner opposite fence line West and on line between adjacent section corners. Set 3/4" iron pipe and cap in Waverly Road Witnesses: Nail and Tag in 10" Hickory WNW 50.18 feet; Nail and Tag in 16" W. Cherry SW 53.67 feet; W 1/4 Corner Section 30, T2N, R2W (Set 3/4" iron pipe & cap) is 80.55 feet South.
- An Act 132 survey in Liber 2, Page 107 recorded on Feb. 2, 1980 by Richard W. Steadman, P.S. 11370. "Set 3/4" iron pipe in 1973 (now in monument box) Witnesses: 10" Hickory (now stump) N 84° W 50.18 ft.; 16" Wild cherry S 50° W 53.67 ft.; 6" Hickory N 88° W 52.64 ft.; 24" Hickory S 57° E 33.48 ft.
- An Act 132 survey in Liber 5, Page 282 recorded on Dec. 27, 1980 by Richard W. Steadman P.S. 11370 "Found 3/4" iron pipe; 10" Hickory Stump N 84° W 50.18 feet; 16" Wild Cherry S 50° W 53.67 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" pipe (3/4" ID) with Cap #11370 in monument box in centerline of Waverly Road on line of fence line to West. Found Nail and Tag #11370 Southeast side 12" Hickory WNW 50.18 feet; West 1/4 Corner, Sec. 30, Aurelius Township, South 80.54 feet. Found pipe was in good condition and placed Cap #28414 over existing cap. Area was previously excavated by Dick Steadman and no further excavation was performed. This surveyor agrees with the position of corner as determined by Dick Steadman. Traversed East section line and measured 2656.25 to M-11 and 2658.70 to M-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1 1/4" (O.D.) Iron pipe in monument box, witnessed by:
Set Nail and Tag #28414 North side 10" Shagbark Hickory S 75° W 34.55 feet
Set Nail and Tag #28414 South side 6" Poplar N 60° E 32.20 feet
Set Nail and Tag #28414 North side 4" Basswood S 40° E 68.88 feet
West 1/4 Corner, Sec. 30, T2N, R2W, Aurelius Township, South 80.54 feet

Signed by Maurice H. Mahieu

Date 11-25-97

Surveyor's Michigan License No. 28414

