

FILED

Copy

94 JUN -3 AM 11:54

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970


EATON TOWNSHIP
For corners in

Form with fields for 'Located In:' (EATON County), 'Corner Code #', and numbered items 1-5 describing survey details.

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 Pg 414

Register of Deeds Stamp & File Number



Grid table with columns A-L and rows 2-13, containing numbers 1-36 and a circled '1' in row 9, column L.

I, Ron Helsel, in a field survey on March 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO record indicates "West corrected between Sections 24 and 25. 39.67 set post at average on true line. Lynn 13" S51 1/2 E 34; and Beech 16" N68W 12". Sylvester Sibley November 1825. No County record of this corner located. Oscar Boss, LS #13574 recorded corner per P.A. 74 in Liber 2, Page 98 on February 20, 1974. LCRC indicates "1/2" iron Found" with witnesses: South 33.02' 1/2" iron found; North 26.96' fence post N.E.S.; S 75° W 88.70 Nail N/S power pole. SEE OTHER SIDE DOCUMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field notes of R. Lester, PS #18998, dated 8/17/1993 indicates the following: "Investigation at this site revealed a 1/2" iron bar 3' South of centerline of Long Road (gravel) on occupation line to North. Excavated 3' diameter hole to depth of 1.5 feet to natural ground. Found nothing but dirt. Set 1/2" bar and identification cap at location of found 1/2" bar and witnessed. Location falls on old occupation line to North and matches deed and survey lines East and West. The 1/2" bar as found is in the location as set by Boss on LCRC in Liber 2, Page 98. Found his nail and tag on East side of old fence post now lying down to North at correct distance and it also matches location of corner as I found it in 1979. I believe this is to be the perpetuated location of the corner L-9 by common accord." SEE OTHER SIDE OF DOCUMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 corner Section 24, T2N, R4W. Set 3/4" x 24" steel bar and cap. Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" on South side 24" apple, N78°W, 124.29' Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side utility pole, S78°W, 88.69' Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" East side 36" oak, N07°E, 54.39' Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side utility pole, S75°E, 120.46'

Signed by Ron Helsel Date March 25, 1994

Surveyor's Michigan License No. 18994 P.A. 345 EATON COUNTY

PEER APPROVED 5/25/94

SECTION "A" OF L-9, T2N, R4W, continued

Various surveys per P.A. 132 of 1970 recorded.

Liber 1, Page 568, December 17, 1973; O. Boss LS #13574. Witnesses same as on P.A. 74 form Recorded Liber 2, Page 98.

Liber 1, Page 742, June 6, 1974; L. Hendryx LS #3276. Indicates corner but no witnesses given.

Liber 2, Page 49, December 3, 1975; R. Lester LS #18998. Witnesses same as on P.A. 74 form recorded Liber 2, Page 98.

Liber 2, Page 98 (same recording numbers as previous LCRC) dated May 26, 1976; O. Boss LS #13574. Witnesses same as on P.A. 74 form Recorded Liber 2, Page 98.

Liber 2, Page 725, July 20, 1978, L. Hendryx LS #3276. Indicates corner but no witnesses given.

Liber 2, Page 726, July 20, 1978, L. Hendryx LS #3276. Indicates corner but no witnesses given.

Liber 3, Page 85, September 25, 1979, R. Lester LS #18998. Corner identified as 1/2" iron with witnesses: Boss nail and tag in East side fence post, North 26.96'; Boss nail and tag in North side power pole, S75°W, 88.70'; Nail and tag #18998 in South side 12" apple, N80°W, 124.31'; Nail and tag #18998 in South side 6" elm, N50°W, 51.72'

Liber 3, Page 203, August, 1980, A. Williams LS #21275. Indicates corner and witnesses same as on P.A. 74 form recorded Liber 2, Page 98.

Liber 5, Pages 703-704, December 2, 1993, R. Lester LS #18998. Corner identified as 1/2" bar and cap. Witnesses:
 Set galvanized nail and 1 1/4" brass tag stamped "LS 18998" on South side 24" apple, 282° az., 124.31'
 Set galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side utility pole, 259° az., 88.62'
 Set galvanized nail and 1 1/4" brass tag stamped "LS 18998" East side 36" oak, 06° az., 54.40'
 Set galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side new utility pole, 106° az., 120.45'

SECTION "B" OF L-9, T2N, R4W, continued

Field investigation on March 17, 1994 revealed a 1/2" bar and cap #18998 2' South centerline of Long Highway on fenceline North. Excavated a 6' x 6' x 2' deep hole around found 1/2" bar and cap #18998. Found no evidence of prior corner monumentation. Accepted 1/2" bar and cap #18998 as perpetuated location of corner and set 3/4" x 24" steel bar and cap #18994 in steel collar. Left following witnesses:

Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" on South side 24" apple, N78°W, 124.29'
 Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side utility pole, S78°W, 88.69'
 Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" East side 36" oak, N07°E, 54.39'
 Found galvanized nail and 1 1/4" brass tag stamped "LS 18998" North side utility pole, S75°E, 120.46'