

DEC 1 8 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

Copy
97 NOV 26 PM 1:10

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Liber 3 pg 845
Register of Deeds Stamp & File Number

For corners in

<u>EATON COUNTY</u> (County)	Located In:	Corner Code
CARMEL TOWNSHIP	T <u>2N</u> R <u>5W</u>	<u>L-10</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on SEPTEMBER 30, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.
2. THERE IS NO OTHER MENTION OF THE CORNER IN THE EATON COUNTY PUBLIC RECORDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR & CAP "FLUKE" #18988, ON A FENCE LINE TO SOUTH AND 2.5' SOUTH OF AN EAST-WEST FENCE LINE. TRAVERSED IN SECTION 25, T2N, R5W TO FIND THE INTERSECTION OF 1/4 LINES AND FOUND THAT FOUND 1/2" BAR & CAP WAS ON NORTH-SOUTH 1/4 LINE AND 0.5' SOUTH OF MY DETERMINATION OF EAST-WEST 1/4 LINE. EXCAVATED AROUND BAR AND FENCE CORNER AND FOUND VAST AMOUNT OF STONE BUT NO OTHER EVIDENCE OF CORNER. ATTEMPTED TO REPLACE 1/2" BAR WITH STANDARD BAR BECAUSE OF ITS CLOSE PROXIMITY TO INTERSECTION OF 1/4 LINES BUT HIT LARGE STONE AND SET STANDARD BAR 0.5' NORTH AT INTERSECTION OF 1/4 LINES. MEASURED NORTH 2669.07' TO L-9, SOUTH 2660.98' TO L-11, WEST 2651.13' TO K-10 AND EAST 2648.13' TO M-10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-10 T2N, R5W
3/4' BAR & ORANGE PLASTIC CAP IMPRINTED PA 345 PS 25837 2.0' SOUTH OF EAST-WEST FENCE LINE ON FENCE LINE TO SOUTH
SET NAIL & TAG #25837 SOUTH SIDE 36" CHERRY, 226° NAZ, 28.50'
SET NAIL & TAG #25837 IN SOUTH SIDE 17" WHITE OAK, 265° NAZ, 19.61'
SET NAIL & TAG #25837 IN WEST SIDE 14" IRONWOOD, 153° NAZ, 35.68'
SET NAIL & TAG #25837 IN NORTH SIDE 16" ASH, 115° NAZ, 16.70'
SET NAIL & TAG #25837 IN WEST SIDE 6" MAPLE, 205° NAZ, 19.58'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by David L. Clifford
Surveyor's Michigan License No. 25837

Date OCTOBER 13, 1997

P.A. 345 EATON COUNTY
PEER APPROVED 10/14/97 ML