

DEC 1 8 1995

COMMISSION

EATON COUNTY REMONUMENTATION

FILED

COPY

96 OCT 28 AM 9: 21

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **EATON**

(County)

Located In:

Corner Code #

2N 6W

A-10

- 1. Public Land Survey
WEST 1/4 CORNER
SECTION 30
ON RANGE LINE
KALAMO TOWNSHIP
- 2. Property Controlling
in Section
- 3. Miscellaneous
Property in Sec.

T	R	
T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Liber 3, Pg 716

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RICHARD W. STEADMAN

OCTOBER 9

96

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
- 2. COUNTY SURVEYOR OSCAR G. CHURCH, 9-26-1876, (VOL. 2, P. 37) "SET STONE FOR POST" NO WITNESSES GIVEN.
- 3. CORRESPONDING STANDARD CORNER WAS RECORDED BY DOUGLAS W. BONNEMA, PS # 12579, BARRY COUNTY LCRC #462, RECORDED SEPT. 14, 1992, "SET CAPPED REROD ON C/L GRAVEL TO N & S...."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER LOCATION FALLS IN A DEEP ROAD CUT. ALL PREVIOUS MONUMENTATION CAN BE PRESUMED DESTROYED. FOUND IRON FOR STANDARD CORNER AS RECORDED BY BONNEMA. OCCUPATION LINE EAST FROM A-10 HAS BEEN OBLITERATED. TRAVERSED 2 1/2 MILES OF RANGE LINE FROM A-13 TO A-8, TYING IN OCCUPATION LINES FROM SURVEY BY CHURCH. ACCEPTED POSITION OF STANDARD CORNER BY BONNEMA N-S; HOWEVER, DETERMINED CORNER SHOULD BE PLACED ON RANGE LINE DEFINED BY M-9 AND M-11, T2N R7W. PLACED REMON IRON AT MID POINT ON RANGE LINE BETWEEN RESTORED A-9 AND RESTORED A-11, IN VERY CLOSE CONFORMANCE WITH PROPORTIONAL DISTANCES TO OCCUPATION LINES REMAINING FROM THE SURVEY BY CHURCH. FIELD WORK SUPERVISED BY BRIAN REYNOLDS, PS #31602.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 24" SOLID IRON WITH PLASTIC CAP INSCRIBED "PA 345 PS 11370")
- FOUND NAIL IN THE S. SIDE OF 6" WALNUT N58°W 28.79'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 12" CHERRY S33°W 52.43'
- SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 3"- 5" MAPLE CLUSTER N41°E 28.39'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 12" MAPLE N39°W 47.66'
- SET 20d NAIL W/REMON TAG IN THE N. SIDE OF 3" HICKORY N33°E 13.80'
- SET 20d NAIL W/REMON TAG IN THE S. SIDE OF 6" WALNUT S77°E 5.84'
- SET 20d NAIL W/REMON TAG IN THE S. SIDE OF 6" HICKORY S57°E 11.95'
- POSITION RECORDED BY BONNEMA (FOUND 1/2" IRON) N30°W 11.64'
- CORNER IS APPROXIMATELY 5.5' EAST OF C/L N-S GRAVEL ROAD (CURTIS ROAD)
- M-10 T2N R7W (BARRY COUNTY REMON MONUMENT) NORTH 10.04'



Signed by Richard W. Steadman Date October 17, 1996

Surveyor's Michigan License No. 11370

P.A. 345 EATON COUNTY APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
PEER APPROVED 10/17/96 M REVISED MAY 14, 1975
REVISED JAN., 1983