

DEC 17 1998

FILED

Copy

98 OCT 16 AM 10:26

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

EATON

Located in:

Corner Code #

(County)
KALAMO TOWNSHIP

1. Public Land Survey

T 2N R 6W B-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 950

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DAVID R. LOHR, P.S. in a field survey on APRIL 30 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-9: 1. POST SET BY MUSGROVE EVANS, U.S. DEP. SURVEYOR IN 1826.
WITNESSED BY: BEECH 12" N 21 1/2 E 6 LKS. (3.96')
LYNN 14" S 22 W 11 LKS. (7.26')
NOTES SHOW DISTANCE EAST OF 40.00 CH. (2640.00')
NOTES SHOW DISTANCE WEST OF 41.17 CH. (2717.22')
(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9: TRAVERSED ENTIRE SECTION 30 IN ORDER TO REVIEW INTERIOR CORNERS SET BY CHURCH IN 1876, VOL. 2 PG.37. APPROXIMATED CORNER LOCATION USING CHURCH'S DISTANCES AND LOCATED 2" PIPE FLUSH WITH GROUND SET IN 24" OF CONCRETE AND STONES ON FENCE TO SOUTH AND EAST-WEST. PRORATED POSITION USING CHURCH'S SURVEY OF ITEM A-2 WOULD BE ABOUT 12 FT. WEST X 6 FT. SOUTH OF 2" PIPE. PIPE LIES ABOUT 45 FEET SOUTH OF KALAMO ROAD WHICH IS MUCH LOWER IN ELEVATION AND LIES ALONG A SLOPE LYING SOUTH TO NORTH. I ACCEPTED LOCATION OF 2" PIPE BASED ON CHURCH'S MEASUREMENTS, HOWEVER I BELIEVE THAT EVANS GLO DISTANCES ARE CONTINUED ON BACK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9: SET 3/4" X 24" STANDARD REMON. BAR AND PA 345 CAP #30090 INSIDE 2" PIPE SET IN CONCRETE AND STONES ON FENCES EAST-WEST AND SOUTH. WITNESSED BY:
SET N/T #30090, S/S 18" ASH, AZ. 58-52-25, 22.81'
SET N/T #30090, E/S 8" ELM, AZ. 162-58-40, 13.45'
SET N/T #30090, S/S 8" CHERRY, AZ. 267-08-55, 18.43'
SET N/T #30090, S/S 12" CHERRY, AZ. 299-48-35, 31.42'
TRAV. PT. KA2-34-157 (1/2" IRON) AZ. 335-50-15, 64.42'



Signed by David R. Lohr
Surveyor's Michigan License No. 30090

Date 9-18-98

P.A. 345 EATON COUNTY
PEER APPROVED 6/23/98 M

B-9 KALAMO PART A CONTINUED

2. CORNER REFERENCED IN SURVEY BY OSCAR CHURCH, COUNTY SURVEYOR.
DATED SEPT. 1876 AND RECORDED IN VOL. 2 PG. 37. AS "STAKE, FOS"
NO WITNESSES GIVEN. SURVEY SHOWS DISTANCE EAST OF 40 CH.(2640.00') AND
DISTANCE WEST OF 45.00 CH. (2970.00')
3. NO OTHER REFERENCES FOUND.

B-9: KALAMO PART B CONTINUED

INACCURATE, AS USING EVANS DISTANCES TO PRORATE WOULD MOVE LOCATION OF
CORNER 112 FT. WEST OF 2" PIPE. SET 3/4" X 24" STANDARD REMON. BAR AND PA 345 CAP
#30090 INSIDE 2" PIPE SET IN CONCRETE AND STONES ON FENCES EAST-WEST AND SOUTH.
MEASURED EAST 2657.57 FT., SOUTH 2605.01 FT., AND WEST 2963.22 FT.

SURVEY &
REMONUMENTATION

DEC 17 1998

SECTION