

DEC 09 1999

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970 99 AUG 17 AM 9:09

For corners in

EATON (County)

Located In:

Corner Code #

KALAMO TOWNSHIP

Table with 5 rows and 3 columns: Item description, Survey type (S/T), and Corner Code # (C-11).

LINDA M. TWITCHELL REGISTER OF DEEDS EATON COUNTY, MICH.

LIBER 4 PAGE 33

Register of Deeds Stamp & File Number

Index table with columns A-M and rows 1-13. Cell (11, B) contains a dot.

I, DAVID R. LOHR, in a field survey on MAY 5, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. POST SET BY MUSCROVE EVANS, U.S. DEPUTY SURVEYOR IN 1826. WITNESSED BY: TAM 9", N 58° E, 12 LKS. (7.92') TAM 9", S 25 1/2° W, 5 LKS. (3.30') NOTES SHOW DISTANCE NORTH AND SOUTH OF 40.00 CH. (2640.00)
2. CORNER REFERENCED IN SURVEY BY OSCAR CHURCH, COUNTY SURVEYOR, DATED MAY 18, 1875 AND RECORDED IN VOLUMN 1, PAGE 226, AS "STAKE, FOS" NO WITNESSES GIVEN. SURVEY SHOWS DISTANCE EAST OF 40.385 CH. (2665.41') AND SOUTH OF 39.85' CH. (2630.10')
3. CORNER REFERENCED IN SURVEY BY OSCAR CHURCH, COUNTY SURVEYOR, DATED JUNE, 1878? AND RECORDED IN VOLUMN 1, PAGE 230, AS "SEE PAGE 226". NO WITNESSES GIVEN. SURVEY SHOWS DISTANCE EAST OF 40.38 CH. (2665.08') AND NORTH OF 40.25 CH. (2656.50') NOTE: COULD NOT FIND ANY PAGE 226 IN ANY OF THE OLD COUNTY SURVEYORS RECORDS.
4. CORNER REFERENCED IN SURVEY BY OSCAR CHURCH, COUNTY SURVEYOR, DATED SEPT. 26, 1876 AND RECORDED IN VOLUMN 2, PAGE 37, AS "SEE, SEC. 29, OLD BOOK." (ITEM A-3??) NO WITNESSES GIVEN. NO DISTANCES SHOWN.
5. CORNER REFERENCED IN SURVEY BY M.H. BAILEY, COUNTY SURVEYOR, DATED APRIL 29 AND 30, 1879 AND RECORDED IN VOLUMN 2, PAGE 82, AS "FOUND OLD CORNER STAKE AND STONES FOR NEW CORNER." NO WITNESSES GIVEN. SURVEY SHOWS DISTANCE EAST TO 1/8 CORNER OF 20.18 CH. (1331.88')
6. NO OTHER REFERENCES FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION AND FOUND REMAINS OF ANCIENT FENCE POST SET IN STONES ON EAST-WEST FENCE LINE AND FENCELINE TO SOUTH. EAST-WEST FENCE RUNS ALONG THE SOUTH SIDE OF OLD "WILDT ROAD" ROAD-BED WHICH ENDS ABOUT 675 FT. WEST OF THIS LOCATION. "WILDT ROAD" IS NOT IN SERVICE AND HAS NOT BEEN FOR MANY YEARS. FOUND REMAINS OF ANOTHER EAST-WEST FENCE ABOUT 32 FT. NORTH. EXCAVATED AREA 2 FT. X 2 FT. X 1 FT. DEEP AROUND OLD WOOD POST, BUT FOUND NOTHING MORE. WATER TABLE IS 2 INCHES BELOW GRADE AT THIS LOCATION. EXCAVATED ANOTHER AREA 3 FT. X 3 FT. X 3 FT. DEEP ON CENTERLINE OF OLD ROAD-BED AND 16 FT. NORTH OF WOOD POST, FOUND NOTHING. EXCAVATED ANOTHER AREA 4 FT. X 4 FT. X 1.5 FT. DEEP ON NORTHERLY FENCELINE 32 FT. NORTH OF WOOD POST, FOUND NOTHING. EXCAVATED AREA 2 FT. X 6 FT. X 1 FT. DEEP, ALONG NORTHERLY FENCELINE, 18.8 FT. WEST OF NORTH-SOUTH OCCUPATION LINE, FOUND NOTHING. TRAVERSED ENTIRE SECTION AND SET CORNER BY SINGLE PROPORTION MEASUREMENT NORTH AND SOUTH, ON NORTH-SOUTH OCCUPATION LINE AT A POINT 21.72 FT. NORTH OF WOOD POST, BASED ON CHURCH'S DISTANCES OF 1875. MEASURED NORTH, 2663.30'; SOUTH, 2636.82'; EAST, 2637.72' AND WEST, 2675.33'. CORNER FALLS ALONG NORTH EDGE OF TWO-TRACK TRAIL (OLD ROAD-BED). SET STANDARD 3/4" X 24" REMON. BAR WITH 2 1/2" PA #345 ALUMINUM CAP MARKED P.S #30090.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11, T2N, R6W, KALAMO TOWNSHIP, EATON COUNTY. SET STANDARD 3/4" X 24" REMON. BAR/CAP BY SINGLE PROPORTIONAL MEASUREMENT NORTH AND SOUTH ON EXISTING OCCUPATION ALONG NORTH-SOUTH FENCELINE. WITNESSED BY: SET N&T #30090, W/S 6"ASH, S 40° E, 20.55' SET N&T #30090, NE/S TW. 15" MAPLE, S 09° E, 35.82' SET #4 REBAR (TRAV. PT. #KA2-9-139), S 06° W, 21.72' SET N&T #30090, E/S 6" ASH, S 14° W, 43.16' SET N&T #30090, E/S 6" ASH, S 40° W, 16.16' BEARINGS GIVEN ARE MAGNETIC.



Signed by David R. Lohr

Date 7/17/99

Surveyor's Michigan License No. 30090