

**SURVEY & REMONUMENTATION**

FILED  
COPY

APR 27 1995

94 DEC -1 AM 9:42

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
**CHESTER TOWNSHIP**

For corners in

EATON

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 3N    R 5W    Corner Code # F-4  
    T    R  
    T    R  
    T    R
- 2. Property Controlling    S    T    R  
    in Section                S    T    R
- 3. Miscellaneous            S    T    R  
    Property in Sec.         S    T    R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

LINDA M. TWITCHELL  
REGISTER OF DEEDS  
EATON COUNTY, MICH.

WBER 3 Pg 562

Register of Deeds Stamp & File Number

I, Maurice H. Mahieu, in a field survey on October 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
No Corner was set in GLO survey.

No other evidence found to indicate corner was ever set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set 3/4" x 24" iron rod with cap #28414, P.A. 345 at the intersection of lines connecting the North and South, and the East and West 1/4 Corners. Measured North 2,643.16 feet to F-3, East 2,643.61 feet to G-4, South 2,641.91 feet to F-5, and West 2,642.00 feet to E-4. Corner falls in 100' ± wide clearcut for a North-South Consumers Power Company easement. Consumers Power Company has no information on this corner. Corner falls 7'± West of a downed North-South fence line and 2'± North of a downed East-West fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 3/4" x 24" iron rod with cap #28414 PA 345, witnessed by:
- Set Nail and Tag #28414 South side 12" Ash, East 60.67 feet
- Set Nail and Tag #28414 North side 12" Hickory, S 74 deg. W 43.39 feet
- Set Nail and Tag #28414 South side 15" Cherry, S 66 deg. W 59.70 feet
- Set Nail and Tag #28414 South side 10" Cherry, West 47.89 feet



Signed by Maurice H. Mahieu Date 11-29-94  
 Surveyor's Michigan License No. #28414

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197  
 REVISED MAY 14, 197  
 REVISED JAN. 198

P.A. 345 EATON COUNTY  
 PEER APPROVED 4/23/94 M