

FILED

copy

97 AUG 12 PM 12:38

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (EATON), Located In (CHESTER TOWNSHIP), Corner Code # (G-8), and sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 793

Register of Deeds Stamp & File Number

4. Lot No.
5. Private Claims

I, RON HELSEL, in a field survey on MAY 20, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column G and row 8.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL MONUMENT: POST SET BY ORANGE RISDON, U.S. DEPUTY SURVEYOR, MAR. 1827. WITNESSED AS BEECH 24", NORTH 11 LINKS & BEECH 9", S11W, 9 LINKS.

- 1) VOL. 1, PAGE 242, OCT. 28, 1878, COUNTY SURVEYOR, OSCAR CHURCH CALLED FOR A STONE BUT DID NOT RECORD WITNESSES.
2) A SURVEY WAS RECORDED IN LIBER 1, PAGES 314, 355, 356, & 437 ( ALL THE SAME SURVEY WITH REVISIONS), DATED MAR 20, 1973, BY R. HELSEL NO. 18994. THE CORNER WAS NOT FOUND AND THE SURVEY WAS TIED TO CORNERS G-7 AND G-9.
3) A SURVEY WAS RECORDED IN LIBER 3, PAGE 466, DATED 9-14-82, BY ROBERT REED NO. 19004. SURVEY TIED TO CORNERS C 7 AND G-9.

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1/2" REBAR AND CAP NO. 18988 1 FOOT EAST OF CENTERLINE OF MULLIKEN ROAD AND OPPOSITE AN OLD ANCHOR POST HOLE SURROUNDED WITH FIELD STONES, 31 FEET TO THE EAST. LOCATION IN A ROAD CUT AREA. EXCAVATED A HOLE 6" TO 8" BELOW GRAVEL INTO CLAY ROAD BED AND FOUND NO FURTHER EVIDENCE OF A CORNER OR ACCESSORIES. SURVEYOR FLUKE MEASURED SOUTH, 2643.30 FEET TO G-9. TRAVERSED NORTH, 2656.27 FEET TO G-7. ACCEPTED THIS POSITION AS FAITHFUL PERPETUATION OF THE CORNER, SUPPORTED BY THE OLD ANCHOR POST HOLE AND REMNANT FENCE TO THE EAST. SET 3/4" FORM PIN AND CAP STAMPED P.A. 345, P.S. NO. 18994 AND MONUMENT BOX TO THE ASPHALT SURFACE OF MULLIKEN ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 3/4" x 24" FORM PIN AND CAP 1.0 FEET CENTERLINE OF MULLIKEN ROAD.
SET NAIL AND TAG NO. 18994, N/SIDE 14" MAPLE ABOVE CAP NO. 18988, AZ. 286 DEG., 37.12 FEET
SET NAIL AND TAG NO. 18994 NW/SIDE 12" WOOD MAIL BOX POLE, AZ. 218 DEG., 27.23 FEET
SET NAIL AND TAG NO. 18994 SE/SIDE 20" BOX ELDER, AZ. 234 DEG., 98.44 FEET
SET NAIL AND TAG NO. 18994 W/SIDE UTILITY POLE NEXT TO PHONE RISER, AZ. 161 DEG., 55.35 FEET
SET NAIL AND TAG NO. 18994 S/SIDE 6" ELM, EAST, 43.2 FEET
OLD ANCHOR POST HOLE, EAST, 31 FEET
MEAS. NORTH 2657.27 FEET TO G-7
MEAS. WEST 2631.77 FEET TO F-8
MEAS. EAST 2638.42 FEET H-8



Signed by [Signature] Date July 18, 1997
Surveyor's Michigan License No. 18994

P.A. 345 EATON COUNTY
PEER APPROVED 7/22/97 M

LIBER 3 PAGE 794

A (CONTINUED)

- 4) SEVERAL UNRECORDED SURVEYS BY KD FLUKE NO. 18988, DATED FROM DEC. 21, 1991 TO JUNE 5, 1993, JOBS 91-57 D TO 91-57 L AND 93-41"A", WITNESSED THE CORNER AS: SET 1/2" ROD WITH R.L.S. CAP #18988. SURVEYS FURNISHED BY L. CHRISTENSON, NO. 30890
- |                                  |         |
|----------------------------------|---------|
| S19E, 55.35, TEL. POLE AND RISER | (FOUND) |
| S36W, 27.07, MAIL BOX #4587      | (FOUND) |
| N68W, 36.93, MAPLE 12"           | (FOUND) |
| N89E, 39.09, BOX ELDER 5"        | (GONE)  |