

EATON COUNTY REMONUMENTATION

FILED

copy

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 26 PM 2: 30

For corners in  
**EATON**

(County)

Located In:

Corner Code ##

3N 6W

D-2

1. Public Land Survey

T \_\_\_ R \_\_\_

VERMONTVILLE TWP.  
CENTER 1/4 COR. SEC. 5

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

LINDA M. TWITCHELL  
REGISTER OF DEEDS  
EATON COUNTY, MICH.

L.3 Pg 667

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**BRIAN REYNOLDS**

21 JULY

95

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6												
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1. GENERAL LAND OFFICE: CORNER NOT SET BY GENERAL LAND OFFICE SURVEY

2. COUNTY SURVEYOR OSCAR C. CHURCH, SURVEY OF A PARCEL IN THE SOUTHWEST 1/4 OF SECTION 5, VOL. 2, P. 30, IMPLIES A BREAKDOWN OF SECTION. NO REFERENCE TO THIS CORNER IN NOTES.

NO OTHER HISTORICAL DATA, PUBLIC OR PRIVATE, COULD BE FOUND FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND INTERSECTION OF FENCES, EXCAVATED, AND FOUND NOTHING. AFTER COMPLETE TRAVERSE OF SECTION 5, TYING IN OCCUPATION ACCEPTED FENCE CORNER AS BEST EVIDENCE OF CORNER POSITION.

SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT AT FENCE CORNER.

TO	C-2	S89°23'08"W	2657.97'
TO	D-1	N0°26'43"E	2669.61'
TO	D-3	S0°13'13"W	2651.85'
TO	E-2	N89°26'38"	2660.51'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD EATON COUNTY REMON IRON AND PLASTIC CAP INSCRIBED "PA 345 31602"

SET 20d NAIL WITH PLASTIC TAG IN THE SOUTH SIDE OF A 10" MAPLE N85°W 15.81'  
 SET 20d NAIL WITH PLASTIC TAG IN THE EAST SIDE OF A 22" MAPLE DUE SOUTH 18.25'  
 SET 20d NAIL WITH PLASTIC TAG IN THE NORTH SIDE OF A 14" HICKORY S89°E 20.54'  
 SET 20d NAIL WITH PLASTIC TAG IN THE SOUTHEAST SIDE OF A 12" ASH S43°W 42.44'  
 SET 20d NAIL WITH PLASTIC TAG IN THE NORTHEAST SIDE OF A 20" BEECH N45°W 61.80'  
 CORNER IS IN LINE WITH FENCE LINE EAST  
 0.2' WEST OF A NORTH SOUTH FENCE



Signed by

*[Handwritten Signature]*

Date

12/21/95

Surveyor's Michigan License No.

31602

345 EATON COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

PEER APPROVED 9/28/95 *[Signature]*