

SURVEY & REMONUMENTATION

DEC 9 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

Copy

99 OCT 12 AM 9:02

For corners in

<u>EATON COUNTY</u>	Located In:	Corner Code #
(County)		
ONEIDA TOWNSHIP		
1. Public Land Survey	T <u>4N</u> R <u>4W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 4 PAGE 67

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on AUGUST, 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1. CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY

2. EATON COUNTY ROAD COMMISSION GRID MAP CALLS FOR CORNER TO BE A STONE AND IRON; IRON ON SOUTH SIDE; COR. POST, WNW, 39.55'; COR. POST, EAST, 27.55';

3. EATON COUNTY ROAD COMMISSION GRID MAP CALLS FOR M-10, T4N, R5W, TO BE A STONE AND IRON; IRON ON SOUTH SIDE; ONEIDA CORNER, SOUTH, 11.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND NOTHING ON CENTERLINE OF COCHRAN ON OCCUPATION LINE TO EAST, 11' SOUTH OF M-10, T4N, R5W. EXCAVATED 18" DIAMETER 48" DEEP AND HIT STONE WITH MAGNETIC READING TO SOUTH OF STONE. ACCEPTED STONE AS CORNER AND SET STANDARD BAR & CAP ABOVE IT ON STANDARD LINE 11.00 FEET SOUTH OF M-10, T4N, R5W. MEASURED NORTH, 2647.36' TO A-9. MEASURED SOUTH, 2650.24' TO A-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 T4N, R4W

3/4" X 24" STEEL BAR & 2 1/2" ALUMINUM CAP IMPRINTED PA 345 25837 EATON COUNTY IN MONUMENT BOX

FOUND NAIL & TAG #12034 (FRED WHITE) IN WEST SIDE UTILITY POLE, N24°E, 236.23'

SET NAIL & TAG #28409 (RON ENGER) IN SOUTH ROOT 40" OAK, N84°E, 613.33'

FOUND NAIL & TAG #12034 IN WEST SIDE UTILITY POLE, S31°E, 187.58'

3/4" X 24" STEEL BAR & 2 1/2" ALUMINUM CAP IN MON. BOX (M-10, T4N, R5W), NORTH, 11.00'



Signed by David Clifford

Date AUGUST 21, 1999

Surveyor's Michigan License No. 25837

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT., 1985

P.A. 345 EATON COUNTY
PEER APPROVED 9/21/99 M