

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

copy

For corners in

EATON
(County)

Located in:

Corner Code #

94 JUN 15 AM 10:29

Oneida Township

1. Public Land Survey

T 4N R 4W

K-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

L3-P429

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

R. W. Steadman, in a field survey on May 22, 1994,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 1). Original monument: wood post set by Orange Risdon, U. S. Deputy Surveyor
in 1827; bearing trees: 8" Maple S54°E 45 lks. and 6" Elm S48°W 16 lks.
- 2). In Record of Surveys, Vol. 2, Page 100, in a June 10, 1879 survey, Count.
Surveyor M. H. Bailey notes "1/4 on W. side of section found government
survey (bearing tree?) and the stake".

(Continued on back)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike in monument box in center of State Hwy. M-100/Hartel Rd
opposite remnants of fences running East and West. Removed spike and dug
through bottom of monument box but found nothing. Road is built on approx-
imately 5 feet of fill in this area.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced railroad spike with standard Eaton County Remonumentation 3/4" smoc
iron rod and cap stamped "P.A. 345, PS 11370" in monument box to mark the
corner, and took the following witnesses (bearings are magnetic):

Chiseled a cut on "I" of "EJIW" in center of Manhole Cover N80°E 27.66'
Chiseled a cut on "I" of "EJIW" in center of Manhole Cover N68°W 28.59'
Set nail and tag 11370 in E. side Telephone Pole S16°W 144.53'

(Continued on back)

signed by Richard W. Steadman

Date May 23, 1994

Surveyor's Michigan License No. 11370

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28,
REVISED MAY 14,
REVISED JAN.,

P.A. 345 EATON COUNTY,
PEER APPROVED 5/25/94 M

K-8, T4N, R4W

Part A - Continued

- 3). 3-04-81: Certified Survey Map (L3-P265), J. A. Porter L.P.S. 19003 notes "W 1/4 Corner, Section 24, T4N, T4W, Oneida Twp., Eaton Co., MI. (Previously Recorded)". (Register of Deeds has no record of a previous recording of this corner).

Part C - Continued

Set nail and tag 11370 in NW side 24" Poplar N65°E 104.32'
Set nail and tag 11370 in E. side telephone pole N23°W 67.19'
Set nail and tag 11370 in S. side 18" Quad. Willow S88°E 36.75'