

FILED
copy

LAND CORNER RECORDATION CERTIFICATE 97 DEC -5 AM 10: 17
Filing Requirement of Act 74, Mich. P.A. 1970

Oneida Township
For corners in Eaton
(County)

Located In:	Corner Code #
T 4N R 4W	M-9
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 876

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Section
- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Larry A. Bryan, in a field survey on September 8, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9, T4N, R4W
- 1. Corner set in Original Government Survey by Orange Risdon, Deputy Surveyor, in January 1827, "Set post Cor. Sec. 24 & 25, Sugar 63 S30°W, 13, Beech 11 N14°W, 43. G.L.O. distance from M-9 to A-9, T4N, R3W, is 14.52' North (22 links).
- 2. County Survey Records, unnamed surveyor, dated Nov. 18, 1868 (Volume 1 Page 30) calls for "F.O.B.T."
- 3. County Survey Records by M.H. Bailey, dated June 10, 1879 (Volume 2 Page 100) calls for "iron sleigh shoe 3 feet long for the stake" with no witnesses given.

(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9,
Found axle shaft in monument box ±3' South of centerline of Mt. Hope Highway & on centerline of Royston Road. All of the witnesses listed above remain except for the apple tree & the anchor posts as called for by the Road Commission (item #4) & check with location of monument. Measured 14.48' North to A-9, T4N, R3W. Dug ±2' into monument box & found no other evidence. Accepted axle shaft as perpetuated location of M-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9, T4N-R4W
- Set standard Remonumentation 3/4" form pin & cap "P.A. 345 L.S. 25832" over found axle shaft in monument box as noted above
- Found M.D.S.H. nail & tag in Northwest side power pole, S45°W, 45.94'
- Found nail & tag #11370 in Southeast side power pole, S45°W, 45.79'
- Found M.D.S.H. nail & tag in East side power pole, N45°E, 51.30'
- Found N.G.S. survey marker "23012 MDOT surveys 1976", N45°W, 46.74'
- Found nail & tag in South side 24" Walnut, N50°E, 68.80'
- Found nail & tag #31603 (Douglas K. Richardson) in North side power pole, S70°E, 99.
- Found axle shaft in monument box, A-9, T4N, R3W, North, 14.48'



Signed by Larry A. Bryan
Surveyor's Michigan License No. 25832

Date 11-26-97

P.A. 345 EATON COUNTY
PEER APPROVED 10/14/97 ML

A:) continued

4. Marginal note of the Eaton County Road Commission copy of the Original Government Survey notes in 1918 by H.A. Williams shows Sec. Cor. 24-25 as a stone witnessed by: Anc. Post N36 1/2°E 57.2', Anc. Post S61 1/2°E 36.3', Anc. Post S47 1/2°W 48'.
5. Steadman, P.S. #11370, survey recorded in Liber 1 of Surveys, Page 654, dated July 5, 1974 shows "Set axle & monument box over stone" with witnesses: Power pole, SW, 45.62', 14" Apple, NE, 85.53', 16" Walnut, ENE, 68.89'.
6. White, P.S. #12034, survey recorded in Liber 2 of Surveys, Page 820, dated October 12, 1978 shows corner as "Found axle shaft in mon. box" with witnesses: S45°W 45.75' N&T Power pole, N50°E 68.91' N&T 15" Walnut, N30°E 85.64' N&T 15" Pear, N45°W 46.72' U.S.G.S. marker.
7. L.C.R.C. recorded by Ron Helsel, P.S. #18994, in Liber 2 of Corners, Page 588, dated October 30, 1978 calls for same monument & witnesses as #6 above.
8. L.C.R.C. recorded by Richard W. Steadman in Liber 2 of Corners, Page 743, dated October 15, 1981 with field work done on May 22, 1972, calls for same monument & witnesses as #5 above. Steadman's notes indicate that he found anchor post hole to Northeast & Southwest which he used to locate long pointed stone 3.2' below surface with dishes around it.
9. Steadman survey recorded in Liber 3 of Surveys, Page 679, dated Feb. 17, 1984 shows "Found axle in monument box" with same witnesses as #5 above.
10. White survey recorded in Liber 4 of Surveys, Page 543, dated April 14, 1988 shows corner & calls for L.2 Pg. 743.
11. White survey recorded in Liber 4 of Surveys, Page 546, dated August 24, 1988 shows corner & calls for L.2 Pg. 743.
12. Christensen, P.S. #30890, survey recorded in Liber 5 of Surveys, Page 648, dated 8-15-93 shows corner & calls for L2 Pg 743.