

DEC 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

copy
98 NOV 10 PM 12: 21

SECTION

For Corners in EATON Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 4N R 6W _____
 1/4 CORNER COMMON TO T _____ R _____
 SECTIONS 33 & 34 T _____ R _____
 SUNFIELD TOWNSHIP T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 974

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 9 MAY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: ORANGE RISDON, D.S., 1827 (R6W, P.620) "40.00 SET 1/4 SEC. POST" TAM 10 N50E 20 Do. 12 S71W 6
- COUNTY SURVEYOR RECORDS: NO NAME OR DATE (V.1, P.17) "STONE & C" NO WITNESSES GIVEN
- COUNTY SURVEYOR RECORDS: FRANK DAVIS, NO DATE (V.1, P.88-89) "SEE PAGE 17 F O B T" NO WITNESSES GIVEN
- COUNTY SURVEYOR RECORDS: FRANK DAVIS, 18 FEB, 1870 (V.1, P.90-91) "SEE PAGE 17" NO WITNESSES GIVEN
- COUNTY SURVEYOR RECORDS: OSCAR CHURCH, 2 MARCH 1874 (V.1, P.194-195) "SEE PAGE 17" NO WITNESSES GIVEN
- COUNTY SURVEYOR RECORDS: OSCAR CHURCH, 20 APRIL, 1876 (V.2, P. 28-29) "STONE SET BY DAVIS" NO WITNESSES GIVEN
- LAND CORNER RECORDATION CERTIFICATE: BY LARRY BRYAN, P.S., #25832 (L.3, P.780) "SET 1/2" BAR & CAP IN CENTERLINE OF ROUND LAKE ROAD "SET NAIL & TAG NORTH SIDE CORNER POST EAST 33.44' SET NAIL & TAG WEST SIDE 8" ASH S55°E 23.45' SET NAIL & TAG NORTH SIDE 6" ASH S40°E 26.33' SET NAIL & TAG EAST SIDE 8" ELM S10°W 51.93' PRIVATE NOTES OF LARRY BRYAN FROM THE ABOVE SURVEY INDICATE THAT G-12 WAS SET AT MID POINT AND ON LINE BETWEEN G-11 & G-13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON AND ONE WITNESS BY BRYAN (ELM SOUTHWEST). TRAVERSE OF THE EAST LINE OF SECTION 33 CONFIRMS IRON BY BRYAN TO BE AT THE MID-POINT AND ON LINE BETWEEN REMONUMENTED G-11 & FOUND IRON USED BY BRYAN AT G-13. EXCAVATED WITH BACKHOE, CENTERED ON POSITION BY BRYAN, 12'+/- NORTH-SOUTH AND 5'+/- EAST-WEST. AT A DEPTH OF 2'+/- FOUND OLD LOGS TO CORDUROY ROAD. AT A DEPTH OF 2.5'+/- FOUND A LARGE FLAT SIDED STONE (ROUGHLY 22"X 18"X 10") LYING FLAT. ALSO FOUND A NUMBER OF 6"- 8" STONES MOSTLY UNDER LARGE STONE SCATTERED BETWEEN 2.5' AND 4.5' DEEP. AT A DEPTH OF 4.5'+/- ON THE VERY TOP OF THE PEAT LAYER, FOUND THE BROKEN BASE TO AN OLD CROCK. FOUND CROCKERY WAS DIRECTLY UNDER LARGE STONE. ACCEPTED FOUND CROCKERY AND STONES AS CORNER POSITION PERPETUATED BY COUNTY SURVEYORS FRANK DAVIS AND OSCAR CHURCH. AT THE POSITION OF FOUND CROCKERY AND STONES, SET 1/2" CAPPED IRON "REYNOLDS 31602" AT A DEPTH OF 4.5'+/- IN THE TOP OF THE PEAT AND RAISED TO 6" BELOW ROAD GRADE WITH A STANDARD EATON COUNTY REMONUMENTATION MONUMENT WITH ALUMINUM CAP STAMPED "31602"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD EATON COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP "31602".
FROM REMONUMENTED G-12 TO POSITION RECORDED BY BRYAN N20°11'02"W 1.39'
FROM REMONUMENTED G-12 TO REMONUMENTED E-12 N89°15'48"W 5259.72'
FROM REMONUMENTED G-12 TO REMONUMENTED G-11 N00°39'29"E 2653.15'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH ROOT OF A 20" WILLOW S82°E 19.50
SET 20d NAIL W/PLASTIC TAG IN THE WEST ROOT OF A 16" WILLOW S51°E 22.04'
FOUND NAIL W/METAL TAG IN THE EAST SIDE OF AN 8" ASH S17°W 50.89'
CORNER LIES ROUGHLY ON NORTH-SOUTH GRAVEL CENTERLINE
1'+/- SOUTH OF FENCE RUNNING EAST



P.A. 345 EATON COUNTY
PEER APPROVED 6/23/98 M

Signed by [Signature]
Surveyor's Michigan License No 31602

Date 11-2-1998