

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 34 N. R. 4 W.	K-1; L-1; L-2; L-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 20, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

L-3
Set DNR mon. & cedar post
in place of well point
10" Maple N30°E 31.3
5" Maple N75°E 22.0


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Found 3/4" pipe at closing corner at G.L.O. measure from standard corner.
- L-1 Set by proportionate measurement, midpoint on line, between section corners. Falls 8.65' W of S¼ of Sec. 36, T. 35 N., R. 4 W.
- L-2 Set corner at calculated intersection of true ¼ lines. Old fence corner about 10' south and 18' west of corner.
- L-3 Found well point, buried, about 7' W of center of old N-S township road grade, in line with old fence N'ly. Falls within 5' of midpoint on line and was probably the result of old county surveyor's survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	L-1	L-2
Set DNR mon. in place of 3/4" pipe	Set DNR mon. & red-top post	Set 5/8" rerod w/RLS cap & red-top post
10" Basswood S20°W 11.0	12" Maple N35°W 56.6	10" Maple S28°E 16.8
6" Maple S63°E 16.75	18" Twin Maple N05°W 58.1	12" Maple S45°W 1.8
SE Cor. 35 T35-4W East 17.0		

SIGNED BY Kenneth J. Ostling DATE 6/27/77
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

EMMET COUNTY