

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 34 N. R. 4 W.	M-1; M-2; M-3
2. PROPERTY CONTROLLING IN SECTION 1	T. 34 N. R. 4 W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 20, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~
 C. (continued)

7
 Set 5/8" rebar & RLS cap-red top post
 14" Hemlock N39°E 23.0
 11" Maple N11°W 10.5


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-1 Found large rock on end at fence intersection N-S-E-W in line roads N and E. Apparently used in Wakenhut survey of Section 36.
- M-2 Found 1/2" pipe as established by Larsen 1969 survey.
- M-3 Found 1" pipe at corner and a rock on end just N of pipe. Fence N-E-W old road S.
- 7 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1	M-2	M-3
Set DNR mon. in place of rock	Set DNR mon. in place of	Set DNR mon. in place of 1" pipe
6" Apple N45°E 34.1	1/2" pipe w/cap.	30" Beech S47°W 27.45
PK in Power Pole N05°E 69.6	6" Maple N33°W 4.15	12" Beech S55°E 41.00
	11" Maple S70°W 8.3	8" R. Pine N20°W 71.30

SIGNED BY *Kenneth J. Ostling* DATE 6/20/77
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ EMMET COUNTY