

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W
T 34 NR 4 W

Emmet - Charlevoix COUNTY

DESCRIPTION OF CORNER Closing corner common to Sections 3 and 4
on north boundary of T33N, R4W
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap,
below surface.

WITNESSES TO CORNER

8" Maple - S40E - 8 links
7" Maple - S48W - 58 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found a $\frac{1}{2}$ "x2" iron bar and old stake point at corner, presumably established by Marcus Schaaf, Registered Land Surveyor about 30 years ago. No remaining evidence of government BTs, probably removed in road construction. Corner checks good for line between 1/4 corner west and section corner east.

Corner was placed and witnessed August 25, 1959.

Corner to Sections 33 and 34 on south boundary of T34N, R4W is 50 links east.

SURVEYORS SEAL

SIGNED *Kenneth J. Otting*
REGISTERED LAND SURVEYOR

DATE 8/27/59