

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W
T 34 NR 4 W

~~Emmet-Charlevoix~~ COUNTY

DESCRIPTION OF CORNER Closing corner common to Sections 2 and 3 on
north boundary of T33N, R4W
DESCRIPTION OF CORNER MONUMENT Left 1" pipe in place

WITNESSES TO CORNER

16" Elm - S11W - 37.3 feet

10" Elm - S73E - 66.2 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found 1" pipe in place previously established by Marcus Schaaf, Registered Land Surveyor, from the government BTs. A 30" Elm, recently cut and lying at road-side was identified as the SW government BT about 30 years ago. Corner falls about 10' east of a fence line south.

Corner to Sections 34 and 35, T34N, R4W is 30 links east.

Corner was witnessed August 11, 1959.

SURVEYORS SEAL

SIGNED *Lucretia J. O'Brien* DATE 8/28/59
REGISTERED LAND SURVEYOR