

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 33 NR 4 W
T 34 NR 4 W

Charlevoix-Emmet COUNTY

DESCRIPTION OF CORNER $1/4$ corner on north side of Section 2, T33N, R4W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

BT 7" R. Pine - S81W - 8 links
BT 8" R. Pine - S42E - 100 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement at midpoint, on line between section corners by Forestry Division survey crew while making a survey in T34N, R4W. Unable to locate any previous corner. Falls on north side of E-W road and in line with east edge of county road south.

$1/4$ corner for Section 35, T34N, R4W is 25 links east.

Corner was set and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 8/2/60
REGISTERED LAND SURVEYOR