

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W ✓
T 34 NR 4 W

Charlevoix-Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side Section 3, T33N, R4W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

BT 12" Basswood - S71W - 3 1/2 links

BT 12" Maple - S83E - 8 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement at midpoint, on line between section corners, by Forestry Division survey crew while making a survey in this area. Falls about 20 links south of E-W county road.

1/4 corner for Section 34, T34N, R4W is 40 links east.

Corner was placed and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED *Kenneth Ostling*
REGISTERED LAND SURVEYOR

DATE 8/2/60