

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 3 W.
T 34 NR 4 W

Cheboygan-Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 30 and 25

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" Elm - 875E - 15 links
9" Basswood - 864W - 28 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of T34NR4W. Found a 1" pipe with concrete base in place at corner, previously established by Marcus Schaaf, Reg. Land Surveyor, in 1927. Said by Forestry Division personnel to be one of several along this town line set to perpetuate government corners whose BTs were evident 30 years ago, prior to fire-line construction.

Corner was placed and witnessed September 9, 1959.

SURVEYORS SEAL

SIGNED

Kenneth J. Pettig
REGISTERED LAND SURVEYOR

DATE 9/11/59