

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 34 NR 3 W  
T 34 NR 4 W

Cheboygan-Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 18-19-13-24

DESCRIPTION OF CORNER MONUMENT Left 1" pipe with concrete base  
in place

WITNESSES TO CORNER

16" Maple	-	S46W	-	34½ links
16" Elm	-	N51E	-	55½ links
10" Elm	-	N18W	-	61½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found a 1" pipe in concrete in place, previously established by Marcus Schaaf, Registered Land Surveyor, from government BTs about 30 years ago. Beech remains at site of SW government BT, all others destroyed. Falls in intersection of trail E-W and fireline N-S. Accepted as good corner in this survey.

Corner was witnessed August 25, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 8/28/59  
REGISTERED LAND SURVEYOR