

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 4 W.

Emmet

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 13 and 24

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe below surface

WITNESSES TO CORNER

8" Elm - N10E - 44 links  
12" Elm - N65W - 123 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of this township. Set corner at midpoint, on line, between Section corners. Corner falls in line with general location of roads east and west and south. Could not identify anything for government evidence. Found a 1/2" pipe about 14 links SW of our corner, but presume it to be a P.I. for road construction. Does not conform to other corners for measurement or line. No other NBTs.

Corner was placed and witnessed September 9, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 9/11/59