

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W
T 34 NR 4 W

Emmet - Charlevoix COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 34 and 35
on south boundary of T34N; R4W

DESCRIPTION OF CORNER MONUMENT Left 3/4" pipe in place

WITNESSES TO CORNER

5" Elm - N20W - 72.3 feet
7" R. Pine - N35E - 59.8 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found a 3/4" pipe in place, previously established by Marcus Schaaf, Registered land surveyor, and obviously set at record distance east of the corner to Sections 2 and 3, which was identified. Considered acceptable for control of surveys in this area.

Closing corner common to Sections 2 and 3, T33N, R4W is 30 links west.

Corner was witnessed August 11, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 8/27/59
REGISTERED LAND SURVEYOR