

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W
T 34N R 4 W

Emmet - Charlevoix COUNTY

DESCRIPTION OF CORNER Sections corner common to Sections 33 and 34
on south boundary of T34N-R4W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" Brass cap,
below surface

WITNESSES TO CORNER

8" Maple - M9W - 33 links

Notch in 18" Elm - N42E - 98½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of this township. Set corner at government record measurement east of closing which was restored by previous survey. This point falls in line with very old fence windrow north and checks for proportionate measurement and line to corners east and west. Best available evidence of proper location for corner.

Closing corner common to Sections 3 and 4 on N. Boundary of T33N, R4W is 50 links west.

Corner was placed and witnessed August 25, 1959.

SURVEYORS SEAL

SIGNED *Levett J. Oetting*
REGISTERED LAND SURVEYOR

DATE 8/27/59