

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 4 W.

Emmet

COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner common to Sections 26 and 27

DESCRIPTION OF CORNER MONUMENT Left $1\frac{1}{4}$ " pipe in place

WITNESSES TO CORNER

7" Maple	-	S89E	-	20 $\frac{1}{2}$ links
10" Maple	-	N35W	-	59 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found $1\frac{1}{4}$ " pipe in center of N-S county road, set by unknown surveyor. Unable to identify anything for government BTs, nor can it be proven wrong. Corner falls about 3' south of old fence line west into Section 27. Very likely established prior to construction of road, and was used for road alignment on section line.

Corner was witnessed August 24, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 8/27/59