

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 4 W.

Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13-14-23-24
DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe, below surface of road
WITNESSES TO CORNER

10" Elm	-	S61E	-	46 links
7" Maple	-	S3W	-	83½ links
14" Elm	-	N51W	-	54½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial retracement of this township. Could find no evidence of a previous corner in a thorough search of the road intersection. Set corner on line over 1/4 corner and section corner west, making the half miles of equal length. This places the corner very near to the centerline of the road north, and would place the 1/4 corner to Sections 13 and 24 in the centerline of the road south. Proportionate measurement was not considered since it would place the corner too far east to conform with the roads or the 1/4 corner south, which is considered a good corner. Falls about 5' north of the apparent centerline of the present E-W county road at this point.

Corner was placed and witnessed August 25 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 8/27/59
REGISTERED LAND SURVEYOR