

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34. NR. 4. W. . .

Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26-27-34-35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

22" Elm - N61E - 35½ links

6" Maple - S61W - 43½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this township. Could find no evidence of a previous corner. Set corner on straight line over 1/4 and section corner north, at proportionate measurement between 1/4 corner north and section corner south. This point falls near center of N-S county road, and conforms very nearly to old field edge west. Did not consider double proportion since great distance between corners and extremely hilly terrain would make this method quite unreliable. It seem quite possible the road could have been constructed to a previous corner, evidence of which has been destroyed.

Corner was placed and witnessed July 27, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* - DATE 8/1/60 -  
REGISTERED LAND SURVEYOR