

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34. NR. 4 W. . .

Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22-23-26-27

DESCRIPTION OF CORNER MONUMENT 1"x24" pipe below surface.

WITNESSES TO CORNER

16" W. Spruce - S47W - 57 links

20" Elm - N42W - 65 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial retracement of this township. Restored corner by proportionate measurement for latitude, in approximate center of road for longitude. Unable to locate a previous corner. This point falls near the centerline intersection of N*S*E*W roads, places the 1/4 line fence north at midpoint, and places the three corners between 26 and 27 on a straight line.

Corner was placed and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 8/1/60