

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 4 W.

Emmet

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 23-24-25-26

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
below surface

WITNESSES TO CORNER

12" Elm - S52E - 27 links

14" Elm - S81W - 101 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial retracement of this township. Could find no evidence of previous corner in cut section of E-W county road. Placed corner by proportion east and west, in center of E-W co. road for latitude, which makes the half miles north of equal measurement and falls in line with faint evidence of old township road grade south.

Corner was placed and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostberg*  
REGISTERED LAND SURVEYOR

DATE 8/1/60