

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 4 W.

Emmet

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25-26-35-36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" R. Pine - S37E - 203 links

5" Cherry - N20E - 27½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was established by double proportionate measurement between corners 1 mile north, south, east, and west by Forestry Division survey crew while making a survey in this township. No evidence of government Bts. Falls at NE corner of field and approximately in line with parts of an old township grade from south.

Corner was placed and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 8/2/60