

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 33 NR 4 W  
T 34 NR 4 W

Charlevoix-Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 35 and 36,  
on south boundary T<sup>34</sup>N, R<sup>4</sup>W

DESCRIPTION OF CORNER MONUMENT 4" pipe with 4" brass cap, below  
surface

WITNESSES TO CORNER

7" Maple - N35W - 69½ links

8" Elm - N49E - 41½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was established by Forestry Division survey crew  
while making a survey in T<sup>34</sup>N, R<sup>4</sup>W. Set corner 20 links east of  
closing corner, as per the government record. Any previous monu-  
ment apparently removed in road construction or maintenance.  
Falls in line with old township road grade north.

Corner to Sections 1 and 2, T<sup>33</sup>N, R<sup>4</sup>W is 20 links west.

Corner was placed and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 8/2/60