

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 NR. 4 W.
T 34 NR 4 W

Charlevoix-Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side Section 35, T34N, R4W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

18" Elm - N79E - 18 links

10" J. Pine - N38W - 11 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement at midpoint, on line between section corners, by Forestry Division survey crew while making a survey in this area. No evidence of previous corner or government B.T.s. Falls about 35 links east of centerline of county road south.

1/4 corner for Section 2. T33N, R4W is 25 links west.

Corner was set and witnessed July 28, 1960.

SURVEYORS SEAL

SIGNED Kenneth Postling
REGISTERED LAND SURVEYOR

DATE 8/2/60