

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Emmet			
(County)	Located In	Corner Code #	
1. Public Land Survey	T 34N R 4W	L-9	
	T 34N R 4W	K-9	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on August 30, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-9 G.L.O. C.W. Cathcart 1840 set quarter section post
 Wit: Sugar 8 N13°E 17 links
 Sugar 6 S01°W 9 links

K-9 G.L.O. C.W. Cathcart 1840 set post corner to sections 23,24,25 and 26.
 Wit: Lynn 12 N80°W 8 links
 Sugar 6 S45°E 30 links

Liber 3, Page 134 Michael Trowbridge P.S. #27483 Found a 1 1/2" pipe for the corner.

Wit: Power pole AZ 16° 80.93'
 Sign Post AZ 114° 17.72'
 6" Maple AZ 95° 39.34'
 22" Maple AZ 263° 45.17'
 20" Maple AZ 284° 50.20'

July 1960, Kenneth J. Ostling R.L.S. #10068 reestablished corner by using proportionate measure East and West and in the center of the East-West county road for latitude
 Wit: 12" Elm S52°E 27 links
 14" Elm S81°W 101 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-9 Found a 1/2" bar fitting Michael Trowbridge witnesses.

K-9 Re-established the Northwest corner of section 25 by doubling over the West half of the North line of section 26 East and holding the center of the East-West county road for latitude. This position seems to fit K.J. Ostling measurements in section 25 reasonably well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Set 1" X 32" iron pipe with P.S. cap #33981
 Wit: 7" Maple S85°E 39.25'
 22" Maple S83°W 45.09'
 10" Maple S05°W 82.02'
 P.P. with tag #41009 N21°E 80.92'
 Centerline of Road going south West 9.0'
 Centerline E-W road North 30.0'

K-9 Set 5/8" X 32" iron rod with P.S. cap #33981
 Wit: 2" R. Pine N25°E 31.93'
 8" Maple N48°W 43.02'
 12" J. Pine S40°E 71.30'
 12" Cherry S07°W 12.06'

Signed by:

Carl T. Kiiskila

Date:

12-9-04

Surveyor's Michigan License No.:

33981

