

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Emmet		Located In	
(County)			Corner Code #
1. Public Land Survey	T	34N	R 4W
	T	34N	R 4W
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl T. Kiiskila, in a field survey on August 7, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-9 G.L.O. John Mullett 1840 set post corner sections 24 and 25. Wit: Beech 10 S47°W 27 links  
Beech 9 N30°E 37 links

M-11 G.L.O. John Mullett 1840 set post corner sections 25 and 36. Wit: Sugar 16 S27°W 22 links  
Beech 10 N30°W 12 links

Marcus Schaaf R.L.S. #3104 (1927) set 1" pipe in concrete from government B.T. remains.

Marcus Schaaf R.L.S. #3104 (1930) restored corner from government evidence.

Kenneth J. Ostling R.L.S. #10068 September 1959 Found M. Schaaf 1" pipe he added a 4" brass cap  
Wit: 7" Maple S71°E 18 ½ links  
6" Maple N22°E 42 ½ links  
10" Basswood S47°W 35 links

Kenneth J. Ostling R.L.S. #10068 July 1960 reestablished M. Schaaf corner position he set a 1" pipe with 4" brass cap.  
Wit: 20" Beech N59°E 33 links  
6" Maple S42°E 29 links  
10" Ironwood N24°W 51 ½ links

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

M-9 Found 1" pipe with broken off brass cap

M-11 Set 5/8" X 32" iron with P.S. cap #33981 from K.J. Ostling witnesses.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-9 Found 1" Pipe with broken brass cap  
Wit: 12" Basswood S55°W 23.07'  
12" Maple N75°W 13.51'  
14" Maple N54°E 25.92'  
12" Maple S67°E 12.19'

M-11 Set 5/8" X 32" iron rod with P.S. cap #33981  
Wit: 28" Beech N67°E 22.65'  
14" Ironwood N19°W 34.65'  
8" Twin Maple S34°E 19.70'  
16" Maple S38°W 23.60'  
½" bar w/ P.S. cap #12020 N25°W 3.04'

Signed by:

*Carl T. Kiiskila*

Date:

12-9-04

Surveyor's Michigan License No.:

33981

