

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:

Emmet
(County)

Located In

Corner Code #

1. Public Land Survey		T	34N		R	4W		M-10
		T			R			
2. Property Controlling in Section	S	25	T	34N	R	4W		7
	S		T		R			
3. Miscellaneous Property in Section	S		T		R			
	S		T		R			

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on August 2, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10 John Mullett 1840 set quarter section post
 Wit: Beech 10 S27°E 52 links
 Beech 7 N09°E 28 links

7- This corner position was not established during the original government survey.

Marcus Schaaf R.L.S. #3104 set a 1" pipe in concrete for this corner in 1927. Dug pits Northeast and Southwest for witnesses.

September 1959 Kenneth J. Ostling R.L.S. #10068 found a 1" pipe in concrete for the corner he added a 4" brass cap.
 Wit: 7" Elm S75°E 15 links
 9" Basswood S64°W 28 1/2 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-10 Reestablished East quarter corner of section 25 using Marcus Schaaf's pit Southwest 33' and K. J. Ostling Elm stump East 9.9'

7- Established the Northeast corner of the Southeast quarter of the Northeast quarter of section 25 as per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Set 5/8" X 32" iron rod with P.S. cap #33981
 Wit: 12" Maple N36°W 48.95'
 16" Maple S39°W 36.51'
 14" Maple N60°E 26.09'
 10" twin Basswood S22°E 28.46'
 Set 5/8" X 32" cir in pit S53°W 33.09'
 Rotten hardwood stump East 9.9'±
 Blue Carsonite post East 10±
 Centerline of N-S road West 4'±

7- Set 5/8" X 32" iron rod with P.S. cap #33981
 Wit: 1" Pin in monument box S08°E 16.00'
 14" Maple N13°W 39.25'
 5" Maple N50°E 38.04'
 10" Maple S40°E 71.94'
 8" Maple S19°W 54.37'
 Centerline of E-W road South 15'±
 Centerline of N-S trail East 3'±

Signed by:

Carl T. Kiiskila

Date:

12-9-04

Surveyor's Michigan License No.:

33981

