

**SURVEY &
REMONUMENTATION**

MAR 04 1998

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE 97 DEC 29 PH 3:09
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>EMMET</u> (County)	Located In:	Corner Code #
	RESORT	TOWNSHIP
1. Public Land Survey	T <u>34N</u> R <u>5 W</u>	<u>A-6</u>
	T _____ R _____	_____
ECRP# 143A	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Glenn A. Sizer
REGISTER OF DEEDS

LIBER A PAGE 18
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Richard E. Oelke, in a field survey on 19 December, 1997
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-6..... 1/4 Corner bet.. secs. 13 &18, T34N, R5W

See Outline of Corner History on back.

Palmer found stone in 1902... Wilcoxon recovered stone in 1946... Miller fd iron in 1960 which was set by Feindt over stone, with broken crockery alongside, he replaced iron with concrete mon. and EC standard cap... This has been used to the present.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. OELKE
ECR.P. REP.
12-27-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6..... 1/4 Corner bet.. secs. 13 &18, T34N, R5W

Found concrete monument in mon box 3' S of CL of Intertown Rd. & 6' E of CL of Cemetery Rd South as presently traveled...

WITNESSED AS FOLLOWS:

N37°E 43.38' p.p., tagged with a MDSH flasher in SE face
S48°W 47.93' p.p., tagged with a MDSH flasher in NW face

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6..... 1/4 Corner bet.. secs. 13 &18, T34N, R5W

Replaced old cap with a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful and faithful perpetuation of the original corner.

NEW WITNESSES AS FOLLOWS:

N38°E 46.55' p.p., tagged 33983 in SE face
S51°E 42.43' p.p., tagged 33983 in NE face
N56°W 69.47' 16" spruce tagged PS# 33983 in SW face

Signed by R.E. OELKE Date 19 December 1997
Surveyor's Michigan License No. 33983



EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 143

34-5-A6
T34N R6W 1/4 CORNER COMMON TO SECTIONS 13/18
INTERTOWN ROAD

Date	Surveyor	Found	Witnesses
1840	GLO	Set post	1) S07°E 15L 8" Beech 2) N27°W 25L 10" Maple
1902	Palmer	found stone with "x"	
1946	Wilcoxon	Fd. Stone with (X) S. & E. of road Int. File (83-34) survey for D. Gokee	
1960	T. Miller	L.C.R.C., Fd. iron pipe set by feindt over notched stone, also found crockery around stone, replaced with concrete monument and Emmet County Standard marker.	
1960	G. Young	Fd. E.C.S.M. in road junction. File (E-289)	3) N35.5°E 39.6' P.P. 4) N52°W 115.7' SE corner house
1963	G. Young	Fd. E.C.S.M. File #487 & #483	
1970	Koivisto	Found E.C.S.M.	5) N40°E 43.39' p.p. 6) S50°E 42.37' anchor pole. 7) S55°W 47.92' p.p.
1971	J. Green	Fd. E.C.S.M. Survey for Goldsmith	6) SE 42.29' anchor Pole 8) SW 46.58' "T" iron 9) NW 46.75' Conc. Monu.
1976	J. Green	Land Corner Recordtion Cert. L1-P245	10) SE 79.70' 14" Birch 11) S-SE 108.00' 12" Birch 12) SW 61.70' P.P.
1971-1976	J. Green	Fd. E.C.S.M. Surveys for Kauffman & Daugavietis	
1977	J. Green	Land Corner Recordation Cert L1-P267	6) S50°E 42.29' anchor pole
1978-1984	J. Green	Fd. E.C.S.M., surveys for Bacon, Weburg, Rasmussen	
1983	Trowbridge	Fd. E.C.S.M. File (Sippel)	witnessed (5, 6, & 7)
1993-1995	Swenor	Fd. E.C.S.M. surveys for Knapp, Allison, & Knapp	

SURVEY &
REMONUMENTATION

MAR 04 1998

SECTION