

MAR 13 2000

SECTION

LETTER A
PAGE 348

EMMET COUNTY REMONUMENTATION PROGRAM

CHRONOLOGY OF GLO CORNER

REMON. CORNER # 218 LCRC # 34-05-C6 TOWNSHIP...BEAR CREEK

CORNER COMMON TO SECTIONS 17/18, T34N, R5W

DATE	SURVEYOR	FOUND/SET	WITNESSES		
1840	GLO Field Notes, Pg 240	Set Post	1) N47°W 2) N60°E	20 lks. 26 lks.	16" Beech 6" Beech
1885	John Keep	Bob Tripp, 1907 notes, pg. 52 - "Established 1/4 post between Sec 17 & 18 from original bearing trees & marked same as above" (Charcoal & Stone with Cross). Did not find these notes in Keep's books.			
1897	S. G. Main Survey Record L 1, Pg 50 & 51	Found Stone	3) N16°E 4) N88°E	212 136	8" Maple 8" Beech
1970- 1975	Schweigert & Young	Found 1" pipe	No Witnesses		
1980	J. H. Green LCRC L 2, Pg 42	Found 1" pipe in monument box at road intersection.	5) N70°W 6) S26°W 7) S58°W 8) N24°W	88.95' 77.88' 65.74' 106.07'	28" Ash 20" Maple Power Pole Power Pole
1977- 1986	J. H. Green Survey Maps	Found 1" pipe in monument box	5) N70°W 6) S26°W 7) S58°W 8) N24°W	88.95' 77.88' 65.74' 106.07'	28" Ash 20" Maple Power Pole Power Pole
1983 & 1984	J. E. Young Survey Maps	Found 1" pipe	5) N70°W 8) N20°W	88.95' 105.96'	28" Ash Power Pole
1984- 1992	M. Trowbridge Survey Maps	Found 1" pipe in monument box	5) N70°W 6) S26°W 7) S58°W 8) N24°W	88.95' 77.88' 65.74' 106.07'	28" Ash 20" Maple Power Pole Power Pole
1997	T. D. Swenor Survey Map	Found 1" pipe in monument box	5) N70°W 6) S26°W 7) S58°W 8) N24°W	88.95' 77.88' 65.74' 106.07'	28" Ash 20" Maple Power Pole Power Pole

