

MAR 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

99 DEC 28 AM 9:38

For corners in EMMET Located In: _____ Corner Code # _____
(County)

Glenn A. Sizer
REGISTER OF DEEDS

- 1. Public Land Survey T 34N R5W C6
ECRP #218
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

LIBER A
PAGE 347

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	1
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

I, Michael A. Trowbridge, in a field survey on _____, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C6, CORNER COMMON TO SECTIONS 17, & 18, T34N, R5W

1840 - GLO set Post. 1885 - John Keep set Stone marked with Cross & Charcoal. 1897 - S. G. Main found Stone. 1970 - Schweigert & Young found 1" Pipe. The 1" Pipe has been used by various surveyors since 1970. SEE CHRONOLOGY ON BACK OF THIS FORM FOR CORNER HISTORY.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
P.E. Oelke
ECRP REP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C6, CORNER COMMON TO SECTIONS 17, & 18, T34N, R5W

Dug below Pipe. Found no evidence of Keep's Stone marked with Cross and Charcoal. Used 1" Pipe as best available evidence of corner.

FOUND WITNESSES

- 5) N70°W (Az.290°) 88.95' 28" Ash, beep in south face of 36" Ash today
- 6) S26°W (Az.206°) 77.88' 20" Maple
- 7) S58°W (Az.238°) 65.74' Power Pole, 24286 cap & nail in southeast face
- 8) N24°W (Az.336°) 106.07' record, 105.98' measure Power Pole, 15401 cap & nail in northeast face

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C6, CORNER COMMON TO SECTIONS 17, & 18, T34N, R5W

The 1" diameter pipe noted above was removed, and replaced with a 2" diameter, 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, which was placed within a standard Emmet County monument box. This position is accepted as the best available evidence of the position of the original corner.

ADDITIONAL NEW WITNESSES

- 9) S62°W (Az. 242°) 65.36' Power Pole, PK-nail in northeast face
- 10) N21°E (Az. 21°) 106.57' Power Pole, 27463 cap & nail in east face
- 11) S14°E (Az. 166°) 63.95' 6" Twin Ash, 27463 cap & nail in west root
- 12) S29°W (Az. 209°) 77.88' 36" Maple, 27463 cap & nail in east face



Signed by Michael A. Trowbridge Date 12-18-99