

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
Emmet	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>34N</u> R <u>5W</u>	<u>J-13</u>	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on July 24, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13- G.L.O. John Mullet 1840 set quarter section post.
 Wit: Cedar 10 N13°W 11 links
 Cedar 8 N22°E 15 links

Liber 1, Page 543-545, Charlevoix Co. Survey Records E.K. Robinson 1888, shows he set the center and the South 1/8 on the North-South one quarter line section 35, from the south 1/4 corner of section 35.

Liber 253, Page 903 Robert Mitchell L.L.S. #28417 set 1/2" X 18" rered with cap P.S. #28417.

Wit: North 14" Cedar 28.31'
 N15°E "T" iron #15410 102.71'
 S25°E 4" Cedar 21.79'
 S49°W 6" W. Pine 34.85'
 S87°W 1" iron pipe 22.90'

Liber 443, Page 487, Emmet County Register of Deeds, July 1990 Mary C. Feindt shows corner. No witnesses or type of monument given.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

J-13 Found a bent 1/2" rered fitting R. Mitchell's and M. Feindt's survey in section 35, T.34N. R.5W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Set 5/8" X 32" rered with P.S. cap #33981 at found bent 1/2" rered.
 Wit: 8" Cedar N46°W 44.95'
 12" Cedar N07°E 28.29'
 8" Cedar S06°E 38.29'
 7" W. Pine S56°W 34.89'
 3/4" Iron pipe S89°W 23.15'
 5/8" X 32" rered w/P.S. cap #33981 N 1/4 cor. sec. 2, T. 33N, R. 5W. S84°E 4.95'



Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-19-02