

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 EMMET COUNTY
 RECORDED

1995 DEC 18 PM 3:50

Glenna B. Sipe
 REGISTER OF DEEDS

LIBER A PAGE 73

Register of Deeds Stamp & File Number

For corners in

EMMET

(County)

Located In:

Corner Code #

RESORT

1. Public Land Survey	T <u>34N</u> R <u>6W</u>	<u>C-3</u>
	T _____ R _____	_____
ECRP #82	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Richard E. Oelke 12 December 95

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

4. Description of original monument and accessories and/or subsequent restoration:

- C-3, Section corner 5,6,7,8 T34N, R6W
 - 1840 GLO Set post 1) N12E 7L 8" birch
 - 2) N30W 17L 6" birch
 - 1981 Chamberlain Set 1" Iron pipe
 - 3) N40E 55.54' 6" cedar
 - 4) S40E 2.34' 9" birch
 - 5) S59W 38.51' 6" maple cluster
 - 6) N40W 62.41' 8" cedar
 - 1993 Oelke Fd. 1" Iron pipe boundary survey



Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3, Section corner 5,6,7,8 T34N, R6W

Found 3/4" id iron pipe as set by Chamberlain in 1981. From CAE Co. memo, corner was established by doubling the 1/4 mi dist. bet. found N 1/16 corner & 1/4 corner on E line of section.

found previously set witnesses

- (4) S40°E, 2.33', 8" Birch, tagged 21566 SW face
- (5) S56°W, 38.47', 6" Maple, fd. sm. nail replaced w/ 33983 tag
- (6) N42°W, 62.62', 12" Cedar, stump

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Emmet County

RE Oelke
 18 DEC 95

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3, Section corner 5,6,7,8 T34N, R6W

Replace 3/4" iron pipe with a 2" dia. 30" long PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

added new witness below

- N29°E, 44.23', 8" Maple, tagged 33983 in SE face
- S65°E, 53.64', 12" Cedar, tagged 33983 in S face
- N648W, 76.47', 6" Cedar, tagged 33983 in SW face

Surveyed by RE Oelke Date 12 DECEMBER 1995

Surveyor's Michigan License No. 33983