

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

96 DEC 31 PM 2:24

For corners in

EMMET
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>34N</u> | R | <u>6W</u> | <u>I-6</u> |
| <u>E.C.R.P #120</u> | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Thomas D. Swenor
REGISTER OF DEEDS
BOOK A
PAGE 41

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Thomas D. Swenor, in a field survey on December 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6,
Quarter Corner common to, Section 14, and Section 15, T34N R6W.

(SEE BACK OF PAGE FOR HISTORY)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5,
Found 1" Iron Bar in Monument and replaced with a 2" diameter, 30" long PVC Pipe with a Base magnet and a standard Brass Emmet County Remonumentation Cap.

THIS CORNER IS ACCEPTED BY THE EMMET COUNTY REMONUMENTATION GROUP AS A FAITHFUL AND CAREFUL PERPETUATION OF THE ORIGINAL CORNER.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. O'Neil
12-30-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 2" diameter, 30" long PVC Pipe with a Base magnet and a standard Brass Emmet County Remonumentation Cap at the 1" Iron Bar in Monument Box. Further reset monument box to preserve corner position.

- (5) S34°W 48.26' - 8" Cedar (found spike nail with 10710 cap on face of tree)
- (6) N68°E 50.60' - Power Pole (found spike nail with 15401 cap)
- (8) N42°W 109.44' - Southeast Corner Garage Foundation.
- (11) S52°W 48.51' - 4" Balsam Fir (found spike nail with 27463 cap)
- (12) N30°E 58.75' - 6" Aspen (found spike nail with 27463 cap)

Signed by Thomas D. Swenor Date December 30, 1996
Surveyor's Michigan License No. 37282

EMMET COUNTY REMONUMENTATION PROGRAM
 CORNER NO. 120
 T34N R6W - 1-6

LIBER A
 PAGE 142

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

| Date | Surveyor | Found | (Witnesses) | |
|------|-----------------|---|-------------|---|
| 1840 | GLO | Set Post | (1) | Cherry 4 N55E 12 |
| | | | (2) | Balsam 7 S70W |
| 1887 | Keep | Set Post | (3) | S71°30'W 36' - 14" Sugar |
| | | | (4) | N15°E 35' - 12" Cedar |
| 1901 | Williams | 1/4 Post | (9) | S40°W 60-1/2 links - 16" Maple |
| | | | (10) | S08°E 82 links - 12" Birch |
| 1973 | J.H. Green | Found 3/4" Pipe (Liber 249, Page 509) | (5) | S38°W 48.25' - 6" Cedar |
| | | | (6) | N68°E 50.08' - Power Pole |
| 1974 | G.E. Young | Found 1" Pipe (Liber 1, Page 182, LCRC) | (5) | S31°W 48.30' - 6" Cedar |
| | | | (6) | N58°E 50.14' - Power Pole |
| 1990 | M.A. Trowbridge | Found 1" Iron Bar in Monument Box (Liber 2, Page 310, LCRC) | (5) | S35°W 48.20' - 8" Cedar |
| | | | (6) | N63°E 50.62' - Power Pole |
| | | | (7) | N03°E 20.18' - Fence Corner |
| | | | (8) | N42°W 109.44' - Southeast Corner Garage Foundation |