

SURVEY & REMONUMENTATION

MAR 04 1998

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

97 DEC 29 PM 3:09

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>EMMET</u> (County)	Located In:	Corner Code #
	RESORT	TOWNSHIP
1. Public Land Survey	T <u>34</u> N R <u>6</u> W	<u>K-5</u>
	T _____ R _____	_____
ECRP# 148	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Glenn B. Sizer
REGISTER OF DEEDS

LIBER A PAGE 175

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Richard E. Oelke, in a field survey on 19 December, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

K-5..... Corner bet.. secs. 11,12,13 &14, T34N, R6W

See Outline of Corner History on back.

Keep set a stone in 1885... The corner was lost, in 1960 Schweigert set, by proration a concrete monument and an Emmet Co. Standard Marker....

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. OELKE
ECRP. REP.
12-27-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5..... Corner bet.. secs. 11,12,13 &14, T34N, R6W

In a monument box, found concrete monument at the intersection of Sterzik and Intertown Roads, in a large cut area.

WITNESSED AS FOLLOWS:

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5..... Corner bet.. secs. 11,12,13 &14, T34N, R6W

Set a standard brass Emmet County Survey Remonumentation Program cap on the concrete monument... This position is accepted as a careful and faithful perpetuation of the original corner.

NEW WITNESSES AS FOLLOWS:

- N51°E 63.05' 14" maple, tagged PS# 33983 in SE face
- S25°E 97.49' 6" ash, tagged PS# 33983 in SW face
- S78°W 31.48' p.p, tagged PS# 33983 in S face
- N10°W 224.40' p.p, tagged PS# 33983 in E face



Signed by R.E. Oelke Date 19 December 1997
Surveyor's Michigan License No. 33983

EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 148

34-6-K5
T34N R6W CORNER COMMON TO SECTIONS 11/12/13/14
STERIZIK ROAD

Date	Surveyor	Found	Witnesses	Notes
1840	GLO	Set post	1) N24°E 7L 5" Beech 2) N26°E 45L 12" Beech	
1885	Keep	Set large stone with " x " and charcoal	Established corner from old bearings	
1902	Palmer	Fd. stone with "X"		
1960	Schweigert	Set Con Mon ECSM in road L C R C filed survey for Resort Township public schools	3) S11°E 242.2' P.P. 4) S84°W 159.9' P.P.	Established by prop. measurement no fences
1962	G. Young	Fd. Corner survey for Ernst		
1966	G. Young	Fd. E.C.S.M. survey for Ray Eppler		
1975	G. Young	Fd. E.C.S.M. survey for Doernenburg		
1981	J. Green	Fd. E.C.S.M. survey for Resort Township L C R C liber 2 page 78	5) S44°E 49.26' 6) N44°E 39.01' 7) S76°W 37.88'	N face of mbt box 1539 SW face of rd sign P.P.
1986	J. Green	Fd. 1/2" re rod in monu. box		
1989	J. Green	Fd. conc. monu. in monu. box survey for Richard Zink		

SURVEY &
REMONUMENTATION

MAR 04 1998

SECTION.