

**SURVEY & REMONUMENTATION**

MAR 04 1998

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

97 DEC 29 PM 3:09

SECTION  
For corners in

<u>EMMET</u> (County)	Located In:	Corner Code #
	<b>RESORT</b>	<b>TOWNSHIP</b>
1. Public Land Survey	T <u>34N</u> R <u>6 W</u>	<u>K-6</u>
<b>ECRP# 147</b>	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Blenna L. Sizer*  
REGISTER OF DEEDS

**LIBER A PAGE 177**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Richard E. Oelke, in a field survey on 19 December, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more that 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-6..... 1/4 Corner bet.. secs. 13 &14, T34N, R6W

See Outline of Corner History on back.

Keep set a stone in 1887... The corner was apparently lost and Palmer set post in 1902... Miller in 1960, found and axle shaft and replaced it with a concrete monument and an Emmet Co. Standard Marker....

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6..... 1/4 Corner bet.. secs. 13 &14, T34N, R6W

In a monument box, found 3/4" pipe above a concrete monument at the intersection of Resort Pike and Intertown Roads, in a probable cut area.

**WITNESSED AS FOLLOWS:**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6..... 1/4 Corner bet.. secs. 13 &14, T34N, R6W

Set a 2" diameter, 14" long PVC pipe with a standard brass Emmet County Survey Remonumentation Program cap above the concrete monument... This position is accepted as a careful and faithful perpetuation of the original corner.

**NEW WITNESSES AS FOLLOWS:**

- N52°E 51.02' p.p., tagged PS# 33983 in SE face
- S60°E 158.72' p.p., tagged PS# 33983 in NE face
- S45°W 40.59' p.p., tagged PS# 33983 in SE face
- N76°W 125.73' p.p., tagged PS# 33983 in N face

Signed by R.E. Oelke Date 19 December 1997  
Surveyor's Michigan License No. 33983



	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EMMET COUNTY REMONUMENTATION PROGRAM  
CORNER NO. 14734-6-K6  
T34N R6W 1/4 CORNER COMMON TO SECTIONS 13/14  
RESORT PIKE ROAD

Date Surveyor	Found	Witnesses
1840 GLO	Set post	
1887 Keep	Established 1/4 post with large stone marked with a cross	
1902 Palmer	Set Cedar Post	
1957 Schweigert	Fd. Iron File (E-62) survey for Schierschmidt	1) N65°E 56.0' PP (PY2-128) 2) S48°W 42.0' Conc. Road Marker
1960 T. Miller	Fd. Axle Shaft Replaced with E.C.S.M. on Con. Mon.	1) N54°E 55.3' P.P. 2) S46°W 41.5' Conc. Rd.
1960 Schweigert	Fd. E.C.S.M. in road survey for Resort Township public schools	1) N54°E 55.3' P.P. 2) S46°W 41.5' Conc. Rd. Marker
1963 G. Young	Fd. Iron in road intersection of Resort Pike & Intertown	
1966 G. Young	Fd. E.C.S.M. File (599)	
1966 G. Young	Fd. E.C.S.M. File (643)	
1972 J. Green	LCRC Liber 1 Page 140 corner K-6 Fd. ECSM	5) N55°E 54.40' P.P. 6) S45°E 60.00' P.P.
1972 J. Green	Fd. E.C.S.M. survey for Scheid & Northern Realty Inc.	
1972 J. Green	Fd. E.C.S.M. survey for Holzscu	
1972 J. Green 1974	Fd. E.C.S.M. survey for Arthur Foster	
1974 G. Young	Fd. Cor. File (1108)	
1975 G. Young	Fd. Cor. File (1216) survey for Doernburg	
1980 G. Young	Fd. Cor. Plat	
1981 J. Green	Fd. E.C.S.M. survey for Resort Twp.	

SURVEY &  
REMONUMENTATION

MAR 04 1998

SECTION