

**SURVEY & REMONUMENTATION**

MAR 04 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

97 DEC 29 PM 3:09

For corners in SECTION

<u>EMMET</u> (County)	Located In: <b>RESORT</b>	Corner Code # <b>TOWNSHIP</b>
1. Public Land Survey  <b>ECRP# 145</b>	T <u>34N</u> R <u>6 W</u> T _____ R _____ T _____ R _____ T _____ R _____	<u>L-7</u> _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

*Glenn B. Sizer*  
REGISTER OF DEEDS

**LIBER A**      **PAGE 179**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Richard E. Oelke, in a field survey on 19 December, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent resstoration:

L-7..... 1/4 Corner bet.. secs. 13 &24, T34N, R6W

See Outline of Corner History on back.

Palmer set post in 1902... Miller in 1960, set Emmet Co. Standard Marker at fence intersection.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7..... 1/4 Corner bet.. secs. 13 &24, T34N, R6W

Found 1-1/4" pipe with Emmet County Standard Marker...

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
R.E. OELKE  
E.C.R.P. REP  
12-27-97

WITNESSED AS FOLLOWS:

S31°W 12' down cedar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7..... 1/4 Corner bet.. secs. 13 &24, T34N, R6W

Replaced 1-1/4" pipe with a 2" diameter, 30" long PVC pipe with a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful and faithful perpetuation of the original corner.

NEW WITNESSES AS FOLLOWS:

- N78°E 30.51' 8" yellow birch, tagged PS# 33983 in SE face
- S10°E 45.84' 6" cedar, tagged PS# 33983 in NE face
- S38°W 45.57' 20" white pine, tagged PS# 33983 in SE face
- N66°W 32.78' 3" tamarack, tagged PS# 33983 in S face

Signed by R.E. Oelke

Date 19 December 1997

Surveyor's Michigan License No. 33983



EMMET COUNTY REMONUMENTATION PROGRAM  
CORNER NO. 145

34-6-L7

T34N R6W 1/4 CORNER COMMON TO SECTIONS 13/24  
RESORT ROAD

Date	Surveyor	Found	Witnesses	Notes
1840	GLO	Set post	1) N 2) S17°E	6L 4" Cedar 5L 6" Balsam
1902	Palmer	Set Cedar Post		
1960	T. Miller	Set E.C.S.M at the intersection of good fences, no evidence of original bts.	3) S31°W 4) N27°W	11.9' 8" Cedar 15.1' 6" Cedar
1960	Schweigert	Fd. E.C.S.M. in fence corner	3) S31°W 4) N27°W	11.9' 8" Cedar 15.1' 6" Cedar

SURVEY &  
REMONUMENTATION

MAR 04 1998

SECTION